




# CITY OF SHERWOOD ROCK CREEK SANITARY TRUNK LINE UPSIZING PROJECT - PHASE I

## FEBRUARY 2021



**VICINITY MAP**  
SCALE: 1"=5,000'

### INDEX OF DRAWINGS

#### GENERAL

- 1 G-1 COVER, INDEX OF DRAWINGS, VICINITY AND LOCATION MAPS
- 2 G-2 GENERAL NOTES
- 3 G-3 ABBREVIATIONS
- 4 G-4 SYMBOLS AND LEGEND
- 5 G-5 SITE/SHEET LAYOUT

#### TRAFFIC CONTROL

- 6 TC-1 TRAFFIC CONTROL PLAN SW TUALATIN-SHERWOOD ROAD
- 7 TC-2 PEDESTRIAN DETOUR PLAN SW TUALATIN-SHERWOOD ROAD

#### EROSION AND SEDIMENT CONTROL


- 8 ESC-1 EROSION AND SEDIMENT CONTROL COVER SHEET AND GENERAL NOTES
- 9 ESC-2 EROSION AND SEDIMENT CONTROL PLAN - 1
- 10 ESC-3 EROSION AND SEDIMENT CONTROL PLAN - 2
- 11 ESC-4 EROSION AND SEDIMENT CONTROL DETAILS - 1
- 12 ESC-5 EROSION AND SEDIMENT CONTROL DETAILS - 2
- 13 ESC-6 DEWATERING PLAN
- 14 ESC-7 DEWATERING DETAILS

#### CIVIL

- 15 C-1 SITE ACCESS, TREE PROTECTION AND REMOVAL PLAN - 1
- 16 C-2 SITE ACCESS, TREE PROTECTION AND REMOVAL PLAN - 2
- 17 C-3 SEWER PLAN AND PROFILE STA 1+00 TO STA 5+00
- 18 C-4 SEWER PLAN AND PROFILE STA 5+00 TO STA 10+00
- 19 C-5 SEWER PLAN AND PROFILE STA 10+00 TO STA 14+54
- 20 C-6 SEWER PLAN AND PROFILE STA A1+00 TO STA A2+18 AND SLOPE DETAIL
- 21 C-7 SW TUALATIN-SHERWOOD RD TRENCHLESS CROSSING PLAN AND PROFILE
- 22 C-8 TRENCHLESS & SETTLEMENT INSTRUMENTATION SECTIONS & DETAILS
- 23 C-9 EARTH PRESSURE DIAGRAM
- 24 C-10 SITE GRADING PLAN
- 25 C-11 CIVIL DETAILS - 1
- 26 C-12 CIVIL DETAILS - 2
- 27 C-13 CLEAN WATER SERVICES STANDARD DETAILS - 1
- 28 C-14 CLEAN WATER SERVICES STANDARD DETAILS - 2

#### LANDSCAPING / SURFACE RESTORATION

- 29 L-1 WORK ZONE RESTORATION AND PLANTING PLAN
- 30 L-2 INVASIVE NON-NATIVE SPECIES REMOVAL AND RESTORATION
- 31 L-3 TEMPORARY IRRIGATION PLAN
- 32 L-4 RESTORATION AND PLANTING DETAILS



**LOCATION MAP**  
SCALE: 1"=1,000'

**murraysmith**

888 SW 5TH AVENUE, SUITE 1170  
PORTLAND, OREGON 97204  
P 503.225.9010



Know what's below.  
Call before you dig.

THIS DESIGN COMPLIES WITH ORS 92.044 (7) IN THAT NO UTILITY INFRASTRUCTURE IS DESIGNED TO BE WITHIN ONE (1) FOOT OF A SURVEY MONUMENT LOCATION SHOWN ON A SUBDIVISION OR PARTITION PLAT. NO DESIGN EXCEPTION NOR FINAL FIELD LOCATION CHANGES SHALL BE PERMITTED IF THAT CHANGE WOULD CAUSE ANY UTILITY INFRASTRUCTURE TO BE PLACED WITHIN THE PROHIBITED AREA.

ATTENTION: OREGON LAW REQUIRES THE CONTRACTOR TO FOLLOW THE RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. THE CONTRACTOR MAY OBTAIN COPIES OF THE RULES BY CALLING THE UTILITY NOTIFICATION CENTER. (NOTE: THE TELEPHONE NUMBER FOR THE OREGON UTILITY NOTIFICATION CENTER IS 503-246-6699.)

# GENERAL NOTES

1. CONTRACTOR SHALL OBTAIN ALL NECESSARY LOCAL, COUNTY, STATE, AND UTILITY CONSTRUCTION PERMITS, AND SHALL CONTACT EACH PERMITTING AGENCY AT LEAST TWO (2) BUSINESS DAYS PRIOR TO STARTING WORK. CONTRACTOR SHALL OBTAIN ALL REQUIRED LICENSES BEFORE STARTING CONSTRUCTION.
2. THE LOCATIONS OF ALL EXISTING UNDERGROUND FACILITIES SHOWN ON THE PLANS ARE BASED ON A FIELD SURVEY AND INFORMATION SUPPLIED BY UTILITY COMPANIES. LOCATIONS ARE NOT GUARANTEED TO BE COMPLETE OR ACCURATE. THE CONTRACTOR SHALL VERIFY LOCATIONS, ELEVATIONS, TYPE AND SIZES OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTING NEW PIPING/CONDUITS AND SHALL ADJUST NEW PIPING/CONDUITS AS REQUIRED. POTHOLING AND TRENCH EXCAVATION SHALL SUFFICIENTLY PRECEDE LAYING OF PIPE TO ALLOW REQUIRED ELEVATION AND ALIGNMENT ADJUSTMENTS TO BE ACCOMPLISHED WITHOUT REWORK. ADJUSTMENTS SHALL BE EXPECTED AND CONSIDERED INCIDENTAL. CONTRACTOR SHALL NOTIFY ENGINEER IMMEDIATELY OF ANY CONFLICTS NOT SHOWN ON THE PLANS AND SHALL KEEP EXISTING UTILITIES IN SERVICE AND PROTECT THEM DURING CONSTRUCTION. WHERE INTERRUPTION OF EXISTING FACILITIES IS REQUIRED, CONTRACTOR SHALL PROVIDE 72 HOUR NOTICE TO ENGINEER AND THE AFFECTED UTILITY. CONTRACTOR SHALL ARRANGE FOR THE RELOCATION OF ANY IN CONFLICT WITH THE PROPOSED CONSTRUCTION.
3. THE CONTRACTOR SHALL COMPLY WITH ALL REQUIREMENTS OF ORS 757.541 TO 757.571. THE CONTRACTOR SHALL NOTIFY EACH UNDERGROUND UTILITY AT LEAST 48 BUSINESS-DAY HOURS, BUT NOT MORE THAN 10 BUSINESS DAYS, PRIOR TO EXCAVATING, BORING, OR POTHOLING.
4. NO ADDITIONAL PAYMENT SHALL BE MADE FOR UTILITY RELOCATION COORDINATION OR DELAYS CAUSED BY UTILITY CONFLICTS. ALL COSTS RELATED TO UTILITY COORDINATION AND RELOCATION, INCLUDING ADDITIONAL POTHOLING, ARE TO BE CONSIDERED INCIDENTAL AND INCLUDED IN THE UNIT PRICES OF THE BID. NO ADDITIONAL PAYMENT SHALL BE MADE FOR REWORK AND DELAYS RESULTING FROM FAILURE TO POTHOLE FOR UTILITIES SUFFICIENTLY IN ADVANCE OF WORK.
5. NOT USED
6. SURVEY DATA COMPILED BY AKS ENGINEERING & FORESTRY. ALL ELEVATIONS SHOWN ARE BASED ON VERTICAL DATUM NAVD 88. CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION SURVEYS. SEE CONTRACT DOCUMENT FOR SURVEY REQUIREMENTS.
7. A LOCAL DATUM PLANE SCALED FROM OREGON STATE PLANE NORTH 3601 NAD83(2011) EPOCH 2010.0000 HAS BEEN ESTABLISHED BY AKS BY HOLDING A PROJECT MEAN GROUND COMBINED SCALE FACTOR OF 1.0001033898 AT A CALCULATED CENTRAL PROJECT POINT WITH GRID VALUES OF (NORTH 453397.31, EAST 7552849.06). THE MERIDIAN CONVERGENCE ANGLE AT THE CALCULATED CENTRAL POINT IS -1°39'09". THE STATE PLANE COORDINATES WERE DERIVED FROM THE TRIMBLE VRS NOW NETWORK.
8. ALL CONSTRUCTION AND MATERIALS SHALL CONFORM TO THE PLANS AND PROJECT SPECIFICATIONS.
9. CONTRACTOR SHALL KEEP AND MAINTAIN A CURRENT SET OF DRAWINGS ON SITE. CONTRACTOR TO KEEP ACCURATE "AS-BUILT" RECORD COPY OF PLANS INDICATING ALL CHANGES IN GRADE, ALIGNMENT, FITTINGS AND MATERIALS INSTALLED AND ANY OTHER UTILITIES OR OBSTACLES NOT SO INDICATED ON THESE PLANS. "AS-BUILT" PLANS TO BE RETURNED TO ENGINEER AT COMPLETION OF PROJECT.
10. CONTRACTOR SHALL MAINTAIN ACCESS TO ALL HOMES AND BUSINESSES AT ALL TIMES. CONTRACTOR SHALL MAINTAIN ACCESS FOR MAIL, TRASH COLLECTION AND SCHOOL BUS SERVICES AT ALL TIMES. PROVIDE WRITTEN NOTICE TO ALL PROPERTY OWNERS AT LEAST TWO BUSINESS DAYS IN ADVANCE OF WORK IN AND/OR CROSSING OF DRIVEWAYS.
11. CONTRACTOR SHALL NOTIFY THE ENGINEER AND OWNER 48 HOURS BEFORE STARTING CONSTRUCTION, AND 24 HOURS BEFORE RESUMING WORK AFTER SHUTDOWNS EXCEPT FOR NORMAL RESUMPTION OF WORK FOLLOWING SATURDAYS, SUNDAYS, OR HOLIDAYS. CONTRACTOR SHALL PROVIDE WRITTEN NOTICE TO THE ENGINEER A MINIMUM OF 48 HOURS PRIOR TO ANY TESTING OR REQUIRED INSPECTION.
12. ANY ALTERATION OR VARIANCE FROM THESE PLANS, EXCEPT MINOR FIELD ADJUSTMENT NEEDED TO MEET EXISTING FIELD CONDITIONS, SHALL FIRST BE APPROVED BY THE ENGINEER. ANY ALTERATIONS OR VARIANCE FROM THESE PLANS SHALL BE DOCUMENTED ON CONSTRUCTION FIELD PRINTS AND TRANSMITTED TO THE ENGINEER. ANY PROPOSED CHANGES IN CONSTRUCTION PLANS MUST BE SUBMITTED IN WRITING AND APPROVED BY ENGINEER PRIOR TO COMMENCING WORK.
13. CONTRACTOR SHALL PROTECT ALL PROPERTY CORNERS, SURVEY MONUMENTS AND CONTROL POINTS. SURVEY MONUMENTS OF THIS TYPE DISTURBED DURING CONSTRUCTION SHALL BE REPLACED AT CONTRACTOR'S EXPENSE, WITH APPROPRIATE SURVEYS FILED WITH THE COUNTY SURVEYOR.
14. THE CONTRACTOR SHALL DISPOSE OF ALL REMOVED OR REPLACED MATERIAL AND EQUIPMENT IN ACCORDANCE WITH ALL APPLICABLE REGULATIONS.
15. ALL STRUCTURES, LOTS, LANDSCAPING, SWALES, DITCHES, SIDEWALK, CONCRETE CURB AND GUTTER, ASPHALT CONCRETE, SPEED BUMPS, FENCES, WALLS, MAILBOXES, SIGNS, POLES, GUY WIRES, PIPING, AND UTILITIES DISTURBED DURING CONSTRUCTION TO BE RESTORED PER CITY OF SHERWOOD STANDARDS UNLESS OTHERWISE SPECIFIED. CONTRACTOR SHALL REPAIR ALL UTILITY SERVICES DAMAGED DURING CONSTRUCTION. ALL SUCH REPAIRS SHALL BE CONSIDERED INCIDENTAL TO PIPELINE INSTALLATION.
16. CONTRACTOR SHALL PROTECT TRAFFIC AT ALL TIMES DURING CONSTRUCTION. ALL TRAFFIC CONTROL MEASURES SHALL BE APPROVED BY CITY, COUNTY AND STATE AS REQUIRED AND IN PLACE PRIOR TO ANY CONSTRUCTION ACTIVITIES. THE CONTRACTOR SHALL PROVIDE TRAFFIC CONTROL PLANS TO THE ENGINEER PRIOR TO COMMENCING ANY WORK WITHIN THE PUBLIC RIGHT-OF-WAY. SEE SPECIAL SPECIFICATIONS FOR DETAILS. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING EMERGENCY VEHICLE ACCESS TO ALL PROPERTIES AT ALL TIMES.

17. CONSTRUCTION SHALL BE CONFINED TO PERMANENT EASEMENTS, TEMPORARY CONSTRUCTION EASEMENTS, OR PUBLIC RIGHT-OF-WAY ONLY. WORK SHALL NOT ENCROACH BEYOND THE RIGHT-OF-WAY WITHOUT APPROVAL. IF AREAS OR FEATURES OUTSIDE DESIGNATED CONSTRUCTION ZONES SUSTAIN IMPACT FROM CONTRACTORS ACTIVITIES, CONTRACTOR SHALL RESTORE TO PRECONSTRUCTION CONDITION AT NO COST TO THE CITY.
18. CONTRACTOR TO INSTALL PERIMETER FENCE AROUND THE WORK ZONE AND LIMIT ALL CONSTRUCTION ACTIVITY INSIDE THE WORK ZONE. NO EQUIPMENT OR SOIL DISTURBANCE ALLOWED OUTSIDE THE WORK ZONE.
19. ALL CONCRETE SHALL BE A MINIMUM OF 3300 PSI STRENGTH.
20. NOT USED
21. NOT USED
22. COMPLY WITH OREGON ADMINISTRATION RULE (OAR) CHAPTER 333 RULES FOR REQUIRED WATERLINE - SEWER LINE SEPARATION AND CROSSING REQUIREMENTS.
23. ALL PIPING SHALL HAVE A MINIMUM OF 3 FEET OF COVER FROM TOP OF PIPE TO STREET GRADE OR OTHER FINISH GRADE.
24. AT THE END OF EACH WORK DAY, ALL OPEN TRENCHES SHALL BE BACKFILLED OR ADEQUATELY FENCED AND PROTECTED FROM THE PUBLIC, AND ALL TRENCHES WITHIN STREETS SHALL BE TEMPORARILY PAVED OR AC COLD PATCHED TO THE SATISFACTION OF THE ENGINEER.
25. THE CONTRACTOR SHALL COMPLY WITH ALL CITY OF SHERWOOD REQUIREMENTS FOR WORK IN AND RESTORATION OF CITY STREETS AND RIGHT-OF-WAYS. SEE CURRENT REVISION OF CITY OF SHERWOOD ENGINEERING DESIGN AND STANDARD DETAILS MANUAL FOR DETAILS.
26. CONTRACTOR SHALL INSTALL TEMPORARY CONSTRUCTION ZONE SIGNS AT LOCATIONS TO BE DETERMINED BY ENGINEER 10 DAYS PRIOR TO BEGINNING OF CONSTRUCTION. TEMPORARY SIGNS SHALL BE CONSTRUCTED AS SPECIFIED WITHIN THE SPECIAL SPECIFICATIONS. TEMPORARY SIGNS SHALL BE LOCATED BY ENGINEER.
27. NO UNDERGROUND WORK SHALL BE "BURIED" UNTIL INSPECTED AND APPROVED BY THE CITY OR OWNER'S REPRESENTATIVE.
28. ALL WORK SHALL BE CONDUCTED BETWEEN THE HOURS OF 7:00AM AND 6:00PM ON NON-HOLIDAY WEEKDAYS. LANE CLOSURES WILL ONLY BE ALLOWED BETWEEN THE HOURS OF 8:00AM AND 6:00PM ON NON-HOLIDAY WEEKDAYS. NO SUNDAY WORK WILL BE ALLOWED. SATURDAY WORK MAY BE ALLOWED VIA A CITY APPROVED SATURDAY WORK REQUEST. SATURDAY WORK REQUESTS MUST BE SUBMITTED AT LEAST 72 HOURS IN ADVANCE OF DESIRED WORK DAY.
29. ALL WORK AND MATERIALS SHALL COMPLY WITH ALL APPLICABLE CITY CODES AND STANDARDS, THE OREGON STATE HEALTH DIVISION ADMINISTRATION RULES, A.P.W.A. STANDARDS, AND CITY OF SHERWOOD ENGINEERING DESIGN AND DETAILS MANUAL.
30. CONTRACTOR SHALL RESTORE ALL EASEMENT AREAS ASSOCIATED WITH CONSTRUCTION AS STIPULATED IN EASEMENT AND CONTRACT DOCUMENTS. CITY OR OWNER'S REPRESENTATIVE SHALL PROVIDE CONTRACTOR WITH REFERENCE COPY OF ALL EASEMENT AGREEMENT CONDITIONS.
31. CONTRACTOR TO PROTECT AND MAINTAIN ALL STORM WATER FACILITIES AND STRUCTURES INCLUDING OUTFALLS, PIPES, RIPRAP, AND INLETS. ANY DAMAGE TO STORM WATER FACILITIES SHALL BE REPLACED AT CONTRACTORS EXPENSE.

# ABANDONMENT NOTES

1. AFTER SUCCESSFUL COMPLETION, TESTING, ACCEPTANCE AND UTILIZATION OF THE NEW SEWER, THE EXISTING SEWER SHALL BE ABANDONED IN PLACE.
2. ALL EXISTING SEWER TO BE ABANDONED IN PLACE SHALL BE FILLED WITH CONTROLLED LOW STRENGTH MATERIAL (CLSM) AS SPECIFIED WITHIN THE SPECIAL SPECIFICATIONS. CLSM SHALL BE PUMPED IN AND VOLUME MEASURED TO ENSURE NO VOIDS ARE REMAINING. CLSM SHALL BE FINISHED FLUSH WITH INSIDE FACE OF WALL FOR ALL EXISTING MANHOLES TO REMAIN.
3. MANHOLES NOTED TO BE REMOVED SHALL BE REMOVED IN THEIR ENTIRETY, INCLUDING BASES, SECTIONS, CONES, TOPS AND COVERS. ALL MANHOLE MATERIALS SHALL BE REMOVED FROM THE SITE AND PROPERLY DISPOSED. THE BOTTOM THREE FEET OF MANHOLE EXCAVATION SHALL BE BACKFILLED WITH BENTONITE TO CREATE AN IMPERVIOUS ZONE, THE REMAINING VOID LEFT FROM THE MANHOLE SHALL BE BACKFILLED WITH NATIVE WETLAND SPOILS FROM THE SITE.
4. MANHOLES NOTED TO BE ABANDONED SHALL HAVE THEIR CONES, TOPS AND COVERS REMOVED FROM THE SITE AND PROPERLY DISPOSED. THE EXISTING BASE MAY REMAIN AND EITHER BE FILLED WITH CLSM (MAXIMUM STRENGTH OF 150 PSI) OR PEA GRAVEL. IF THE CONTRACTOR ELECTS TO UTILIZE PEA GRAVEL, THE MANHOLE BASE SHALL HAVE HOLES DRILLED THROUGH THE BOTTOM TO ALLOW DRAINAGE. THE VOID ABOVE THE MANHOLE BASE SHALL BE BACKFILLED WITH NATIVE TOPSOIL FROM THE SITE.

G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-G.dwg G-2 2/2/2021 1:44 PM JUSTIN.DEUEL.23.0s (LMS Tech)

NO.	DATE	BY	REVISION

NOTICE

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU  
DESIGNED

EJJ  
DRAWN

BVO  
CHECKED

RENEWS 12-31-22

**CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1**

**GENERAL NOTES**

PROJECT NO.: 19-2481.402    SCALE: AS SHOWN    DATE: FEBRUARY 2021

SHEET

**G-2**

2 of 32

G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-G.dwg G-3 2/2/2021 1:44 PM JUSTIN.DEUEL.23.0s (LMS Tech)

@	AT	COL	COLUMN	FOM	FACE OF MASONRY	LAV	LAVATORY	PTVC	POINT OF TANGENCY ON VERTICAL	TSP	TRI-SODIUM PHOSPHATE
AASHTO	AMERICAN ASSOCIATION OF STATE HIGHWAY & TRANSPORTATION OFFICIALS	COMB	COMBINATION	FOS	FACE OF STUDS	LB	POUND		CURVE	TST	TOP OF STEEL
AB	ANCHOR BOLT	CONC	CONCRETE	FPM	FEET PER MINUTE	LF	LINEAR FOOT	PV	PLUG VALVE	TW	TOP OF WALL
ABAN(D)	ABANDON(ED)	CONN	CONNECTION	FPS	FEET PER SECOND	LIN	LINEAL	PVC	POLYVINYL CHLORIDE	TYP	TYPICAL
ABS	ACRYLONITRILE BUTADIENE STYRENE	CONST	CONSTRUCTION	FRP	FIBERGLASS REINFORCED PLASTIC	LN	LANE	PVMT	PAVEMENT	UG	UNDERGROUND
ABV	ABOVE / ALCOHOL BY VOLUME	CONT	CONTINUOUS / CONTINUATION	FT	FEET / FOOT	LOC	LOCATION	PWR	POWER	UH	UNIT HEATER
AC	ASPHALTIC CONCRETE	CONTR	CONTRACT(OR)	FTG	FOOTING	LONG	LONGITUDINAL	QTY	QUANTITY	UN	UNION
ACP	ASPHALTIC CONCRETE PAVING	COORD	COORDINATE	FUT	FUTURE	LP	LOW PRESSURE			UNO	UNLESS OTHERWISE NOTED
ADJ	ADJUSTABLE	COP	COPPER	FXTX	FIXTURE	LPT	LOW POINT			USGS	UNITED STATES GEOLOGIC SURVEY
ADJC	ADJACENT	CORP	CORPORATION	G	GAS	LRG	LARGE	RAD	RADIUS	V	VENT / VOLT
AFF	ABOVE FINISHED FLOOR	CORR	CORRUGATED	GA	GAUGE	LS	LONG SLEEVE / LUMP SUM	RC	REINFORCED CONCRETE	VAC	VACUUM
AFG	ABOVE FINISHED GRADE	COS	CITY OF SHERWOOD	GAL	GALLON	LT	LEFT	RCP	REINFORCED CONCRETE PIPE	VB	VACUUM BREAKER
AHR	ANCHOR	CP	CONTROL POINT	GALV	GALVANIZED	LVL	LEVEL	RD	ROAD / ROOF DRAIN	VBOX	VALVE BOX
AL	ALUMINUM	CPVG	CHLORINATED POLYVINYL CHLORIDE	GC	GROOVED COUPLING	LWL	LOW WATER LINE	RDCR	REDUCER	VC	VERTICAL CURVE
ALT	ALTERNATE	CR	CRUSHED ROCK	GFA	GROOVED FLANGE ADAPTER	MAN	MANUAL	REF	REFERENCE	VERT	VERTICAL
AMP	AMPERE	CS	COMBINED SEWER	GI	GALVANIZED IRON	MAT	MATERIAL	REINF	REINFORCE(D)(ING)(MENT)	VFD	VARIABLE FREQUENCY DRIVE
ANSI	AMERICAN NATIONAL STANDARDS INSTITUTE	CSP	CONCRETE SEWER PIPE	GIP	GALVANIZED IRON PIPE	MAX	MAXIMUM	RESTR	RESTRAINED	VOL	VOLUME
APPROX	APPROXIMATE	CT	COURT	GJ	GRIP JOINT	MCC	MOTOR CONTROL CENTER	RFCA	RESTRAINED FLANGE COUPLING	VCP	VITRIFIED CLAY PIPE
APPVD	APPROVED	CTR	CENTER	GL	GLASS	MCP	MASTER CONTROL PANEL		ADAPTER	VTR	VENT THROUGH ROOF
APWA	AMERICAN PUBLIC WORKS ASSOCIATION	CU	CUBIC	GLV	GLOBE VALVE	MECH	MECHANICAL	RM	ROOM	W	WATER
ARCH	ARCHITECTURAL	CULV	CULVERT	GND	GROUND	MET	METAL	RND	ROUND	W/	WITH
ARV	AIR RELEASE VALVE	CV	CONTROL VALVE	GPD	GALLONS PER DAY	MFR	MANUFACTURER	RO	ROUGH OPENING	W/IN	WITHIN
ASCE	AMERICAN SOCIETY OF CIVIL ENGINEERS	CW	CLOCKWISE / COLD WATER	GPH	GALLONS PER HOUR	MGD	MILLION GALLONS PER DAY	R/W	RIGHT-OF-WAY	W/O	WITHOUT
ASSN	ASSOCIATION	CWS	CLEAN WATER SERVICES	GPM	GALLONS PER MINUTE	MH	MANHOLE	RBPBD	REDUCED PRESSURE BACKFLOW PREVENTION DEVICE	W/W	WALL TO WALL
ASSY	ASSEMBLY	CY	CUBIC YARDS	GPS	GALLONS PER SECOND	MIN	MINIMUM	RPM	REVOLUTIONS PER MINUTE	WD	WOOD
ASTM	AMERICAN SOCIETY FOR TESTING & MATERIALS	CYL	CYLINDER LOCK	GR	GRADE	MIPT	MALE IRON PIPE THREAD	RR	RAILROAD	WF	WIDE FLANGE
ATM	ATMOSPHERE	D	DRAIN	GR LN	GRADE LINE	MISC	MISCELLANEOUS	RST	REINFORCED STEEL	WH	WATER HEATER
AUTO	AUTOMATIC	DC	DIRECT CURRENT	GRTG	GRATING	MJ	MECHANICAL JOINT	RT	RIGHT	WI	WROUGHT IRON
AUX	AUXILIARY	DEFL	DEFLECTION	GV	GATE VALVE	MON	MONUMENT / MONOLITHIC			WM	WATER METER
AVE	AVENUE	DET	DETAIL	GRVL	GRAVEL	MOT	MOTOR	SALV	SALVAGE	WP	WORKING POINT / WATERPROOFING
AVG	AVERAGE	DI	DUCTILE IRON	GYP	GYP SUM	MP	MILEPOST	SAN	SANITARY	WS	WATER SERVICE
AWWA	AMERICAN WATER WORKS ASSOCIATION	DIA	DIAMETER	HB	HOSE BIBB	MSL	MEAN SEAL LEVEL	SC	SOLID CORE	WSDOT	WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
B&S	BELL & SPIGOT	DIM	DIMENSION	HC	HOLLOW CORE	MTD	MOUNTED	SCHED	SCHEDULE	SD	STORM DRAIN
BC	BOLT CIRCLE	DIR	DIRECTION	HDPE	HIGH DENSITY POLYETHYLENE	NA	NOT APPLICABLE	SDI	SADDLE	SDL	SADDLE
BD	BOARD	DIST	DISTANCE	HDR	HEADER	NC	NORMALLY CLOSED	SDR	STANDARD DIMENSION RATIO	SECT	SECTION
BETW	BETWEEN	DN	DOWN	HDWE	HARDWARE	NF	NEAR FACE	SHLDR	SHOULDER	SHT	SHEET
BF	BOTH FACE	DR	DRIVE	HGR	HANGER	NIC	NOT IN CONTRACT	SHT	SHEET	SIM	SIMILAR
BFD	BACKFLOW PREVENTION DEVICE	DS	DOWNSPOUT	HGT	HEIGHT	NO / NO.	NORMALLY OPEN / NUMBER	SLP	SLOPE	SLV	SLEEVE
BFILL	BACKFILL	DWG	DRAWING	HH	HANDHOLD	NOM	NOMINAL	SOLN	SOLUTION	SP	SOIL PIPE / SEWER PIPE
BFV	BUTTERFLY VALVE	DWL	DOWEL	HM	HOLLOW METAL	NORM	NORMAL	SPCL	SPECIAL	SP	SPECIAL
BHP	BRAKE HORSEPOWER	DWV	DRAIN WASTE AND VENT	HMAC	HOT MIX ASPHALT CONCRETE	NRS	NON-RISING STEM	SPC(S)	SPECIFICATION(S)	SPG	SPACING
BKGD	BACKGROUND	DWY	DRIVEWAY	HNDRL	HANDRAIL	NTS	NOT TO SCALE	SPL	SPOOL	SPRT	SUPPORT
BLDG	BUILDING	E OR ELEC	ELECTRICAL	HOA	HAND-OFF-AUTO	O TO O	OUT TO OUT	SQ	SQUARE	SQ FT	SQUARE FOOT
BLK	BLOCK	EA	EACH	HOR	HAND-OFF-REMOTE	OC	ON CENTER	SQ IN	SQUARE INCH	SQ YD	SQUARE YARD
BLVD	BOULEVARD	ECC	ECCENTRIC	HORIZ	HORIZONTAL	OD	OUTSIDE DIAMETER	SS	SANITARY SEWER	SST	STAINLESS STEEL
BM	BENCHMARK / BEAM	ECC	ECCENTRIC	HP	HIGH PRESSURE / HORSEPOWER	ODOT	OREGON DEPARTMENT OF TRANSPORTATION	ST	STREET	STA	STATION
BMP	BEST MANAGEMENT PRACTICES	EF	EACH FACE	HPG	HIGH PRESSURE GAS	OF	OVERFLOW / OUTSIDE FACE	STD	STANDARD	STL	STEEL
BO	BLOW-OFF	EL	ELEVATION	HPT	HIGH POINT	OHWM	ORDINARY HIGH WATER MARK	STOR	STORAGE	STR	STRAIGHT
BOC	BACK OF CURB	ELB	ELBOW	HR	HOUR	OPNG	OPENING	STRUCT	STRUCTURE / STRUCTURAL	SUBMG	SUBMERGED
BS	BOTH SIDES	ENCL	ENCLOSURE	HSB	HIGH STRENGTH BOLT	OPP	OPPOSITE	SUCT	SUCTION	SUCT	SUCTION
BSMT	BASEMENT	EOP	EDGE OF PAVEMENT	HV	HOSE VALVE	ORIG	ORIGINAL	SV	SOLENOID VALVE	S/W	SIDEWALK
BTF	BOTTOM FACE	EQ	EQUAL	HVAC	HEATING, VENTILATION, AIR CONDITIONING	OVHD	OVERHEAD	SWD	SIDEWATER DEPTH	SWGR	SWITCH GEAR
BTU	BRITISH THERMAL UNIT	EQL SP	EQUALLY SPACED	HWL	HIGH WATER LINE	P&ID	PROCESS & INSTRUMENTATION DIAGRAM	SYMM	SYMMETRICAL	SYS	SYSTEM
BV	BALL VALVE	EQUIP	EQUIPMENT	HWY	HIGHWAY	PC	POINT OF CURVE	T OR TEL	TELEPHONE	T&B	TOP & BOTTOM
BW	BOTH WAYS	ESMT	EASEMENT	HYD	HYDRANT	PCC	POINT OF COMPOUND CURVE	TAN	TANGENCY	TB	THRUST BLOCK
C	CELSIUS	EW	EACH WAY	HYDR	HYDRAULIC	PCCV	POINT OF CURVATURE ON VERTICAL CURVE	TBM	TEMPORARY BENCHMARK	TC	TOP OF CONCRETE / TOP OF CURB
C TO C	CENTER TO CENTER	EXC	EXCAVATE	I&C	INSTRUMENTATION & CONTROL	PE	PLAIN END	TCE	TEMPORARY CONSTRUCTION EASEMENT	TDH	TOTAL DYNAMIC HEAD
CARV	COMBINATION AIR RELEASE VALVE	EXIST	EXISTING	IAW	IN ACCORDANCE WITH	PERF	PERFORATED	TEMP	TEMPERATURE / TEMPORARY	T&G	TONGUE & GROOVE
CATV	CABLE TELEVISION	EXP	EXPANSION	ID	INSIDE DIAMETER	PERM	PERMANENT	THK	THICK / THICKNESS	THRD	THREAD (ED)
CB	CATCH BASIN	EXP BT	EXPANSION BOLT	IE	INVERT ELEVATION	PERP	PERPENDICULAR	THRU	THROUGH	TP	TEST PIT / TOP OF PAVEMENT / TURNING POINT
CCP	CONCRETE CYLINDER PIPE	EXT	EXTERIOR	IF	INSIDE FACE	PH	PIPE HANGER	TRANS	TRANSITION		
CCW	COUNTER CLOCKWISE	F	FAHRENHEIT	IMPVT	IMPROVEMENT	PI	POINT OF INTERSECTION				
CFM	CUBIC FEET PER MINUTE	F TO F	FACE TO FACE	IN	INCH	PIVC	POINT OF INTERSECTION ON VERTICAL CURVE				
CFS	CUBIC FEET PER SECOND	FAB	FABRICATE	INCC	INCLUDE(D)(ING)	PKWY	PARKWAY				
CHAN	CHANNEL	FB	FLAT BAR	INFL	INFLENT	PL OR P/L	PROPERTY LINE / PLATE / PLASTIC				
CHEM	CHEMICAL	FCA	FLANGED COUPLING ADAPTER	INJ	INJECTION	POC	POINT OF CURVATURE				
CHFR	CHAMFER	FCO	FLOOR CLEANOUT	INSTL	INSTALLATION / INSTALL	POLY	POLYETHYLENE				
CHKV	CHECK VALVE	FD	FLOOR DRAIN	INSUL	INSULATION	PP	POWER POLE				
CI	CAST IRON	FDN	FOUNDATION	INTR	INTERCEPTOR	PRC	POINT OF REVERSE CURVATURE				
CIP	CAST IRON PIPE	FEXT	FIRE EXTINGUISHER	INTR	INTERIOR	PRCST	PRECAST				
CIPC	CAST IN PLACE CONCRETE	FF	FAR FACE	INV	INVERT	PREP	PREPARATION				
CISP	CAST IRON SOIL PIPE	FGL	FIBERGLASS	IP	IRON PIPE	PRESS	PRESSURE				
CJ	CONSTRUCTION JOINT	FH	FIRE HYDRANT	IPT	IRON PIPE THREAD	PRKG	PARKING				
CL OR C/L	CENTER LINE	FIN	FINISH(ED)	IR	IRON ROD	PROP	PROPERTY				
CL2	CHLORINE	FIPT	FEMALE IRON PIPE THREAD	IRRIG	IRRIGATION	PRV	PRESSURE REDUCING VALVE				
CLG	CILING	FITG	FITTING	JT	JOINT	PS	PUMP STATION				
CLJ	CONTROL JOINT	FL	FLOOR LINE	JUNC	JUNCTION	PSIG	POUNDS PER SQUARE INCH GAUGE				
CLR	CLEAR	FLX	FLEXIBLE	KPL	KICK PLATE	PSL	PIPE SLEEVE				
CLSM	CONTROLLED LOW STRENGTH MATERIAL	FLG	FLANGE	KVA	KILOVOLT AMPERE	PSPT	PIPE SUPPORT				
CMP	CORRUGATED METAL PIPE	FLR	FLOOR LINE	KW	KILOWATT	PT	POINT OF TANGENCY				
CMU	CONCRETE MASONRY UNIT	FM	FLOOR	KWY	KILOWATT						
CND	CONDUIT	FO	FORCE MAIN	L	LENGTH						
CO	CLEANOUT	FOF	FACE OF FINISH	LAB	LABORATORY						


NO.	DATE	BY	REVISION

NOTICE

0 1/2 1

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU DESIGNED  
EJJ DRAWN  
BVO CHECKED




CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1

ABBREVIATIONS


PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021

# SECTION AND DETAIL DESIGNATIONS

## SECTION DESIGNATIONS



## DETAIL DESIGNATIONS



\* NOTE: IF PLAN AND SECTION FOR DETAIL CALL-OUT AND DETAIL ARE SHOWN ON THE SAME DRAWING, DRAWING NUMBER IS REPLACED WITH A DASH.

# MISCELLANEOUS PIPING SYMBOLS

- METER
- SLIP-ON JOINT PIPE
- RESTRAINED JOINT PIPE

# TOPOGRAPHIC LEGEND


	EXISTING	PROPOSED
WATERLINE	--- 10"W ---	— 12"DI W —
ELECTRICITY	--- E ---	— E —
GAS	--- 4"G ---	— 4"G —
TELEPHONE/TELEMETRY	--- T ---	— T —
CABLE TELEVISION	--- CATV ---	— CATV —
SANITARY SEWER LINE	--- 8"SS ---	— 8"SS —
SANITARY SEWER FORCE MAIN	--- 6"FM ---	— 6"FM —
STORM DRAIN	--- 8"SD ---	— 8"SD —
CULVERT	====	— 18"D —
ABANDON PIPE		+++++
DRAINAGE DITCH/FLOODWAY BOUNDARY	.....	.....
ROCK CREEK OHWM	-----	
VEGETATED CORRIDOR BOUNDARY	--- VC ---	
WETLAND BOUNDARY	--- W ---	
BARBED WIRE FENCE	--- X X X ---	
CHAINLINK FENCE	--- O O O ---	--- O O O ---
CENTERLINE	--- ---	--- ---
PROPERTY LINE	--- ---	--- ---
EASEMENT	--- ---	--- ---
RIGHT-OF-WAY	--- ---	--- ---
EDGE OF PAVEMENT/AC	--- ---	--- ---
EDGE OF GRAVEL	--- ---	--- ---
CURB	--- ---	--- ---
SIDEWALK	--- S/W ---	--- ---
STRUCTURE OR FACILITY	--- ---	--- ---
CONTOUR MINOR	--- ---	--- ---
CONTOUR MAJOR	--- 200 ---	--- 200 ---
MANHOLE	○	●
CLEAN-OUT	○	
CATCH BASIN/FIELD INLET	⊞	
VALVE	⊗	
GEOTECHNICAL BORING W/ ID NO.	●	
FIRE HYDRANT ASSEMBLY	⊗	
WATER METER	⊞	
PULL BOX/JUNCTION BOX	⊞	
UTILITY POLE	○	
GUY WIRE	└	
LIGHT POST	⊕	
MAILBOX	⊞	
SIGN	└	└
DEWATERING WELL	⊕	
TREE DECIDUOUS	☼	☼
TREE CONIFEROUS	☼	☼
TREE TO BE REMOVED	☼	☼
SURFACE ELEVATION	+ 176.63	+ 176.63
MONUMENT	△	

G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-G.dwg G-4 2/2/2021 1:44 PM JUSTIN.DEUEL.23.0s (LMS Tech)

NO.	DATE	BY	REVISION

NOTICE  
  
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU  
DESIGNED  
 EJJ  
DRAWN  
 BVO  
CHECKED




**CITY OF SHERWOOD  
 ROCK CREEK  
 SANITARY TRUNK LINE  
 UPSIZING PROJECT -  
 PHASE 1**

**SYMBOLS AND LEGEND**

PROJECT NO.: 19-2481.402    SCALE: AS SHOWN    DATE: FEBRUARY 2021

SHEET  
**G-4**  
 4 of 32

G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-G.dwg G-5 2/2/2021 1:44 PM JUSTIN.DEVEL 23.0s (LMS Tech)



PLAN  
SCALE: 1"=60'



NO.	DATE	BY	REVISION

NOTICE  
0 1/2 1  
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU DESIGNED  
EJJ DRAWN  
BVO CHECKED





CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1

SITE/SHEET LAYOUT  
PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021

SHEET  
G-5  
5 of 32

G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-TC.dwg TC-1 1/21/2021 4:46 PM JUSTIN.DEUEL 23.0s (LMS Tech)



**LEGEND**

- TEMPORARY TRAFFIC CONTROL SIGN
- CHANNELIZING DEVICE
- DIRECTION OF TRAVEL
- WORK SPACE

**SIGN LEGEND**

- 1. UTILITY WORK AHEAD  
W21-7 36"x36"
- 2. CENTER LANE CLOSED AHEAD  
W9-3 36"x36"
- 3. RIGHT TURN AHEAD  
W24-1L 36"x36"
- 4. END ROAD WORK  
G20-2 36"x18"
- 5. THRU TRAFFIC KEEP RIGHT  
R4-3A 24"x36"
- 6. NO LEFT TURN  
R3-2 24"x24"

**NOTES:**

1. TEMPORARY TRAFFIC CONTROL SHALL BE IN ACCORDANCE WITH THESE PLANS, CITY AND COUNTY REQUIREMENTS, AND THE LATEST VERSIONS OF THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) AND THE OREGON TEMPORARY TRAFFIC CONTROL HANDBOOK, SPECIFICALLY DIAGRAM 430: DIVERSION INTO A CONTINUOUS LEFT TURN LANE.
2. ALL TRAFFIC CONTROL DEVICES (TCD'S) SHALL BE MUTCD COMPLIANT.

NO.	DATE	BY	REVISION

NOTICE  
 0 1/2 1  
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU DESIGNED  
 EJJ DRAWN  
 BVO CHECKED




**CITY OF SHERWOOD  
 ROCK CREEK  
 SANITARY TRUNK LINE  
 UPSIZING PROJECT -  
 PHASE 1**

**TRAFFIC CONTROL PLAN  
 SW TUALATIN-SHERWOOD ROAD**

PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021

SHEET  
 TC-1  
 6 of 32




G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-TC.dwg TC-2 1/21/2021 4:46 PM JUSTIN.DEUEL 23.0s (LMS Tech)






**SIDEWALK DETOUR**  
SCALE: NTS



**LEGEND**

-  TEMPORARY TRAFFIC CONTROL SIGN
-  BARRIER, SEE NOTE 3
-  WORK SPACE

**SIGN LEGEND**

-  R9-11L  
24"x18"
-  R9-9  
24"x12"
-  R9-11R  
24"x18"

- NOTES:**
1. TEMPORARY TRAFFIC CONTROL SHALL BE IN ACCORDANCE WITH THESE PLANS, CITY AND COUNTY REQUIREMENTS, AND THE LATEST VERSION OF THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD), SPECIFICALLY FIGURE 6H-28: SIDEWALK DETOUR OR DIVERSION.
  2. ALL TRAFFIC CONTROL DEVICES (TCD'S) SHALL BE MUTCD COMPLIANT.
  3. BARRICADES SHALL BE TYPE 1 BARRICADES PER MUTCD FIGURE 6F-7 CHANNELIZING DEVICES.

NO.	DATE	BY	REVISION

NOTICE  
0 1/2 1  
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU  
DESIGNED  
EJJ  
DRAWN  
BVO  
CHECKED




**CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1**

**PEDESTRIAN DETOUR PLAN  
SW TUALTIN-SHERWOOD ROAD**


PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021

SHEET  
TC-2  
7 of 32

# ESC PLAN FOR SITES 1 TO 5 ACRES



**VICINITY MAP**  
SCALE: 1"=5,000'



**SITE MAP**  
SCALE: 1"=1,000'

**PROPERTY DESCRIPTIONS:**

TAXLOTS 25129A000301, 25129A000400, AND 25129D000150, AND SW TUALATIN-SHERWOOD RD R/W, LOCATED IN THE NORTHEAST AND SOUTHEAST 1/4'S OF SECTION 29, TOWNSHIP 2 SOUTH, RANGE 1 WEST, WILLAMETTE MERIDIAN, WASHINGTON COUNTY, OREGON.

**PROJECT LOCATIONS:**

NORTH AND SOUTH OF SW TUALATIN-SHERWOOD RD, APPROXIMATELY 375 FEET EAST OF SW CENTURY DR, SHERWOOD, WASHINGTON COUNTY, OREGON.

LATITUDE: 45.367302°N, LONGITUDE: -122.828534°W

**ATTENTION EXCAVATORS:**

OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THESE RULES FROM THE CENTER BY CALLING 503-232-1987. IF YOU HAVE ANY QUESTIONS ABOUT THE RULES, YOU MAY CONTACT THE CENTER. YOU MUST NOTIFY THE CENTER AT LEAST TWO BUSINESS DAYS, BEFORE COMMENCING AN EXCAVATION. CALL 503-246-6699.

**DEVELOPER**

DEVELOPER: CITY OF SHERWOOD  
CONTACT: BOB GALATI, PE  
ADDRESS: 22560 SW PINE ST  
CITY/STATE: SHERWOOD, OR 97140  
PHONE/FAX: (503) 925-2308

**PLANNING / ENGINEERING / SURVEYING FIRM**

COMPANY: MURRAYSMITH, INC  
CONTACT: BRENDAN O'SULLIVAN, P.E.  
ADDRESS: 888 SW 5TH AVE, SUITE 1170  
CITY/STATE: PORTLAND, OR 97204  
PHONE: (503) 225-9010 FAX: (866) 274-9807

**NARRATIVE DESCRIPTIONS**

**EXISTING SITE CONDITIONS**

CITY OF SHERWOOD UNDEVELOPED LAND CONTAINING AN 18" DIAMETER SANITARY SEWER LINE AND ASSOCIATED MANHOLE STRUCTURES, WETLANDS, AND FLOODPLAINS ASSOCIATED WITH ROCK CREEK; WASHINGTON COUNTY AND CITY OF SHERWOOD PAVED ROADWAY SURFACES AND RIGHT-OF-WAY

**DEVELOPED CONDITIONS**

SITE WILL BE RETURNED TO PRE-CONSTRUCTION CONDITIONS IMMEDIATELY AFTER CONSTRUCTION OF NEW 24" DIAMETER SANITARY SEWER LINE AND ASSOCIATED MANHOLE STRUCTURES AND ABANDONMENT OF EXISTING 18" DIAMETER SANITARY SEWER LINE. THIS INCLUDES THE PLANTING OF NATIVE TREES, SHRUBS, AND SEED MIXES AND REESTABLISHMENT OF EXISTING CONTOURS AND GRADES.

**NATURE OF CONSTRUCTION ACTIVITY AND ESTIMATED TIME TABLE**

- \* CLEARING (FROM JUNE 1, 2020 TO NOVEMBER 11, 2020)
- \* MASS GRADING (FROM JUNE 1, 2020 TO SEPTEMBER 30, 2020)
- \* UTILITY INSTALLATION (FROM JUNE 1, 2020 TO NOVEMBER 11, 2020)
- \* FINAL STABILIZATION (FROM NOVEMBER 12, 2020 TO DECEMBER 31, 2022)

TOTAL SITE AREA:  
3.9 ACRES (169,300 SQ FT)

TOTAL DISTURBED AREA:  
2.0 ACRES (85,800 SQ FT)

IMPERVIOUS SURFACE AREA:  
EXISTING IMPERVIOUS AREA = 24,100 SQ FT  
PROPOSED IMPERVIOUS AREA = 0 SQ FT

**SITE SOIL CLASSIFICATION:**  
5B - BRIEDWELL STONY SILT LOAM  
14 - COVE CLAY  
27 - LABISH MUCKY CLAY  
37B, 37C - QUATAMA LOAM  
43 - WAPATO SILTY CLAY LOAM

THE HAZARD OF EROSION OF ON-SITE SOILS IS SLIGHT. FILL MATERIAL WILL MAINLY BE GENERATED ON-SITE FROM UTILITY TRENCH EXCAVATIONS. THERE WILL BE SOME IMPORT OF GRANULAR MATERIAL USED TO BED THE PIPE AND BACKFILL AROUND MANHOLES. ANY UNUSED EXCAVATED MATERIALS WILL BE HAULED OFF-SITE.

**RECEIVING WATER BODIES:**  
ROCK CREEK AND TUALATIN RIVER DRAINAGE BASINS

**INSPECTION FREQUENCY**

SITE CONDITION	MINIMUM FREQUENCY
1. ACTIVE PERIOD	WEEKLY WHEN STORMWATER RUNOFF, INCLUDING RUNOFF FROM SNOW MELT, IS OCCURRING.  AT LEAST ONCE EVERY MONTH, REGARDLESS OF WHETHER STORMWATER RUNOFF IS OCCURRING.
2. PRIOR TO THE SITE BECOMING INACTIVE OR IN ANTICIPATION OF SITE INACCESSIBILITY.	ONCE TO ENSURE THAT EROSION AND SEDIMENT CONTROL MEASURES ARE IN WORKING ORDER. ANY NECESSARY MAINTENANCE AND REPAIR MUST BE MADE PRIOR TO LEAVING THE SITE.
3. INACTIVE PERIODS GREATER THAN FOURTEEN (14) CONSECUTIVE CALENDAR DAYS.	ONCE EVERY MONTH
4. PERIODS DURING WHICH THE SITE IS INACCESSIBLE DUE TO INCLEMENT WEATHER.	IF PRACTICAL, INSPECTIONS MUST OCCUR DAILY AT A RELEVANT AND ACCESSIBLE DISCHARGE POINT OR DOWNSTREAM LOCATION.
5. PERIODS DURING WHICH DISCHARGE IS UNLIKELY DUE TO FROZEN CONDITIONS.	MONTHLY. RESUME MONITORING IMMEDIATELY UPON MELT, OR WHEN WEATHER CONDITIONS MAKE DISCHARGES LIKELY.

- HOLD A PRE-CONSTRUCTION MEETING OF PROJECT CONSTRUCTION PERSONNEL THAT INCLUDES THE INSPECTOR TO DISCUSS EROSION AND SEDIMENT CONTROL MEASURES AND CONSTRUCTION LIMITS.
- ALL INSPECTIONS MUST BE MADE IN ACCORDANCE WITH DEQ 1200-CN PERMIT REQUIREMENTS.
- INSPECTION LOGS MUST BE KEPT IN ACCORDANCE WITH DEQ'S 1200-CN PERMIT REQUIREMENTS.
- RETAIN A COPY OF THE ESCP AND ALL REVISIONS ON SITE AND MAKE IT AVAILABLE ON REQUEST TO DEQ, AGENT, OR THE LOCAL MUNICIPALITY. DURING INACTIVE PERIODS OF GREATER THAN SEVEN (7) CONSECUTIVE CALENDAR DAYS, RETAIN THE ESCP AT THE CONSTRUCTION SITE OR AT ANOTHER LOCATION.

**STANDARD EROSION AND SEDIMENT CONTROL PLAN DRAWING NOTES:**

1. ALL PERMIT REGISTRANTS MUST IMPLEMENT THE ESCP. FAILURE TO IMPLEMENT ANY OF THE CONTROL MEASURES OR PRACTICES DESCRIBED IN THE ESCP IS A VIOLATION OF THE PERMIT.
2. THE ESCP MEASURES SHOWN ON THIS PLAN ARE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, UPGRADE THESE MEASURES AS NEEDED TO COMPLY WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL EROSION AND SEDIMENT CONTROL REGULATIONS.
3. SUBMISSION OF ALL ESCP REVISIONS IS NOT REQUIRED. SUBMITTAL OF THE ESCP REVISIONS IS ONLY UNDER SPECIFIC CONDITIONS. SUBMIT ALL NECESSARY REVISION TO DEQ OR AGENT.
4. PHASE CLEARING AND GRADING TO THE MAXIMUM EXTENT PRACTICAL TO PREVENT EXPOSED INACTIVE AREAS FROM BECOMING A SOURCE OF EROSION.
5. IDENTIFY, MARK, AND PROTECT (BY FENCING OFF OR OTHER MEANS) CRITICAL RIPARIAN AREAS AND VEGETATION INCLUDING IMPORTANT TREES AND ASSOCIATED ROOTING ZONES, AND VEGETATION AREAS TO BE PRESERVED. IDENTIFY VEGETATIVE BUFFER ZONES BETWEEN THE SITE AND SENSITIVE AREAS (E.G., WETLANDS), AND OTHER AREAS TO BE PRESERVED, ESPECIALLY IN PERIMETER AREAS.
6. PRESERVE EXISTING VEGETATION WHEN PRACTICAL AND RE-VEGETATE OPEN AREAS. RE-VEGETATE OPEN AREAS WHEN PRACTICABLE BEFORE AND AFTER GRADING OR CONSTRUCTION. IDENTIFY THE TYPE OF VEGETATIVE SEED MIX USED.
7. EROSION AND SEDIMENT CONTROL MEASURES INCLUDING PERIMETER SEDIMENT CONTROL MUST BE IN PLACE BEFORE VEGETATION IS DISTURBED AND MUST REMAIN IN PLACE AND BE MAINTAINED, REPAIRED, AND PROMPTLY IMPLEMENTED FOLLOWING PROCEDURES ESTABLISHED FOR THE DURATION OF CONSTRUCTION, INCLUDING PROTECTION FOR ACTIVE STORM DRAIN INLETS AND CATCH BASINS AND APPROPRIATE NON-STORMWATER POLLUTION CONTROLS.
8. ESTABLISH CONCRETE TRUCK AND OTHER CONCRETE EQUIPMENT WASHOUT AREAS BEFORE BEGINNING CONCRETE WORK. DIRECT ALL WASH WATER INTO A PIT OR LEAK-PROOF CONTAINER. HANDLE WASH WATER AS WASTE, CONCRETE DISCHARGE TO WATERS OF THE STATE IS PROHIBITED.
9. APPLY TEMPORARY AND/OR PERMANENT SOIL STABILIZATION MEASURES IMMEDIATELY ON ALL DISTURBED AREAS AS GRADING PROGRESSES AND FOR ALL ROADWAYS INCLUDING GRAVEL ROADWAYS.
10. ESTABLISH MATERIAL AND WASTE STORAGE AREAS, AND OTHER NON-STORMWATER CONTROLS.
11. PREVENT TRACKING OF SEDIMENT ONTO PUBLIC OR PRIVATE ROADS USING BMPs SUCH AS: GRAVELED (OR PAVED) EXITS AND PARKING AREAS, GRAVEL ALL UNPAVED ROADS LOCATED ONSITE, OR USE AN EXIT TIRE WASH. THESE BMPs MUST BE IN PLACE PRIOR TO LAND-DISTURBING ACTIVITIES.
12. WHEN TRUCKING SATURATED SOILS FROM THE SITE, EITHER USE WATER-TIGHT TRUCKS OR DRAIN LOADS ON SITE.
13. USE BMPs TO PREVENT OR MINIMIZE STORMWATER EXPOSURE TO POLLUTANTS FROM SPILLS; VEHICLE AND EQUIPMENT FUELING, MAINTENANCE, AND STORAGE; OTHER CLEANING AND MAINTENANCE ACTIVITIES; AND WASTE HANDLING ACTIVITIES. THESE POLLUTANTS INCLUDE FUEL, HYDRAULIC FLUID, AND OTHER OILS FROM VEHICLES AND MACHINERY, AS WELL AS DEBRIS, LEFTOVER PAINTS, SOLVENTS, AND GLUES FROM CONSTRUCTION OPERATIONS.
14. IMPLEMENT THE FOLLOWING BMPs WHEN APPLICABLE: WRITTEN SPILL PREVENTION AND RESPONSE PROCEDURES, EMPLOYEE TRAINING ON SPILL PREVENTION AND PROPER DISPOSAL PROCEDURES, SPILL KITS IN ALL VEHICLES, REGULAR MAINTENANCE SCHEDULE FOR VEHICLES AND MACHINERY, MATERIAL DELIVERY AND STORAGE CONTROLS, TRAINING AND SIGNAGE, AND COVERED STORAGE AREAS FOR WASTE AND SUPPLIES.
15. USE WATER, SOIL-BINDING AGENT OR OTHER DUST CONTROL TECHNIQUE AS NEEDED TO AVOID WIND-BLOWN SOIL.
16. THE APPLICATION RATE OF FERTILIZERS USED TO REESTABLISH VEGETATION MUST FOLLOW MANUFACTURER'S RECOMMENDATIONS TO MINIMIZE NUTRIENT RELEASES TO SURFACE WATERS. EXERCISE CAUTION WHEN USING TIME-RELEASE FERTILIZERS WITHIN ANY WATERWAY RIPARIAN ZONE.
17. IF A STORMWATER TREATMENT SYSTEM (FOR EXAMPLE, ELECTRO-COAGULATION, FLOCCULATION, FILTRATION, ETC.) FOR SEDIMENT OR OTHER POLLUTANT REMOVAL IS EMPLOYED, SUBMIT AN OPERATION AND MAINTENANCE PLAN (INCLUDING SYSTEM SCHEMATIC, LOCATION OF SYSTEM, LOCATION OF INLET, LOCATION OF DISCHARGE, DISCHARGE DISPERSION DEVICE DESIGN, AND A SAMPLING PLAN AND FREQUENCY) BEFORE OPERATING THE TREATMENT SYSTEM. OBTAIN PLAN APPROVAL BEFORE OPERATING THE TREATMENT SYSTEM. OPERATE AND MAINTAIN THE TREATMENT SYSTEM ACCORDING TO MANUFACTURER'S SPECIFICATIONS.
18. AT THE END OF EACH WORKDAY SOIL STOCKPILES MUST BE STABILIZED OR COVERED, OR OTHER BMPs MUST BE IMPLEMENTED TO PREVENT DISCHARGES TO SURFACE WATERS OR CONVEYANCE SYSTEMS LEADING TO SURFACE WATERS.
19. CONSTRUCTION ACTIVITIES MUST AVOID OR MINIMIZE EXCAVATION AND CREATION OF BARE GROUND DURING WET WEATHER OCTOBER 01 - MAY 31.
20. SEDIMENT FENCE: REMOVE TRAPPED SEDIMENT BEFORE IT REACHES ONE THIRD OF THE ABOVE GROUND FENCE HEIGHT AND BEFORE FENCE REMOVAL.
21. OTHER SEDIMENT BARRIERS (SUCH AS BIOBAGS): REMOVE SEDIMENT BEFORE IT REACHES TWO INCHES DEPTH ABOVE GROUND HEIGHT. AND BEFORE BMP REMOVAL.
22. CATCH BASINS: CLEAN BEFORE RETENTION CAPACITY HAS BEEN REDUCED BY FIFTY PERCENT. SEDIMENT BASINS AND SEDIMENT TRAPS: REMOVE TRAPPED SEDIMENTS BEFORE DESIGN CAPACITY HAS BEEN REDUCED BY FIFTY PERCENT AND AT COMPLETION OF PROJECT.
23. WITHIN 24 HOURS, SIGNIFICANT SEDIMENT THAT HAS LEFT THE CONSTRUCTION SITE, MUST BE REMEDIATED. INVESTIGATE THE CAUSE OF THE SEDIMENT RELEASE AND IMPLEMENT STEPS TO PREVENT A RECURRENCE OF THE DISCHARGE WITHIN THE SAME 24 HOURS. ANY IN-STREAM CLEAN UP OF SEDIMENT SHALL BE PERFORMED ACCORDING TO THE OREGON DIVISION OF STATE LANDS REQUIRED TIMEFRAME.
24. THE INTENTIONAL WASHING OF SEDIMENT INTO STORM SEWERS OR DRAINAGE WAYS MUST NOT OCCUR. VACUUMING OR DRY SWEEPING AND MATERIAL PICKUP MUST BE USED TO CLEANUP RELEASED SEDIMENTS.
25. PROVIDE PERMANENT EROSION CONTROL MEASURES ON ALL EXPOSED AREAS. DO NOT REMOVE TEMPORARY SEDIMENT CONTROL PRACTICES UNTIL PERMANENT VEGETATION OR OTHER COVER OF EXPOSED AREAS IS ESTABLISHED. HOWEVER, DO REMOVE ALL TEMPORARY EROSION CONTROL MEASURES AS EXPOSED AREAS BECOME STABILIZED, UNLESS DOING SO CONFLICTS WITH LOCAL REQUIREMENTS. PROPERLY DISPOSE OF CONSTRUCTION MATERIALS AND WASTE, INCLUDING SEDIMENT RETAINED BY TEMPORARY BMPs.
26. IF VEGETATIVE SEED MIXES ARE SPECIFIED, SEEDING MUST TAKE PLACE NO LATER THAN SEPTEMBER 1; THE TYPE AND PERCENTAGES OF SEED IN THE MIX MUST BE IDENTIFIED ON THE PLANS.
27. ALL PUMPING OF SEDIMENT LADEN WATER SHALL BE DISCHARGED OVER AN UNDISTURBED, PREFERABLY VEGETATED AREA, AND THROUGH A SEDIMENT CONTROL BMP I.E. (FILTER BAG).
28. ALL EXPOSED SOILS MUST BE COVERED DURING THE WET WEATHER PERIOD, OCTOBER 01 - MAY 31.
29. IF WATER OF THE STATE IS WITHIN THE PROJECT SITE OR WITHIN 50 FEET OF THE PROJECT BOUNDARY, MAINTAIN THE EXISTING NATURAL BUFFER WITHIN THE 50-FOOT ZONE FOR THE DURATION OF THE PERMIT COVERAGE, OR MAINTAIN LESS THAN THE ENTIRE EXISTING NATURAL BUFFER AND PROVIDE ADDITIONAL EROSION AND SEDIMENT CONTROL BMPs.

THE PERMITTEE IS REQUIRED TO MEET ALL THE CONDITIONS OF THE 1200-CN PERMIT. THIS ESCP AND GENERAL CONDITIONS HAVE BEEN DEVELOPED TO FACILITATE COMPLIANCE WITH THE 1200-CN PERMIT REQUIREMENTS. IN CASES OF DISCREPANCIES OR OMISSIONS, THE 1200-CN PERMIT REQUIREMENTS SUPERCEDE REQUIREMENTS OF THIS PLAN.

**BMP MATRIX FOR CONSTRUCTION PHASES**

REFER TO DEQ GUIDANCE MANUAL FOR A COMPREHENSIVE LIST OF AVAILABLE BMP'S.

	CLEARING	MASS GRADING	UTILITY INSTALLATION	STREET CONSTRUCTION	FINAL STABILIZATION	WET WEATHER (OCT. 1 - MAY 31ST)
<b>EROSION PREVENTION</b>						
PRESERVE NATURAL VEGETATION	** X	X	X		X	X
GROUND COVER			X		X	X
HYDRAULIC APPLICATIONS					X	
PLASTIC SHEETING		X	X			
MATTING					X	
DUST CONTROL	X	X	X		X	X
TEMPORARY PERMANENT SEEDING					X	X
BUFFER ZONE	** X	X	X		X	X
OTHER:						
<b>SEDIMENT CONTROL</b>						
SEDIMENT FENCE (PERIMETER)	** X	** X	X		X	X
SEDIMENT FENCE (INTERIOR)	** X	** X	X		X	X
STRAW WATTLES			X		X	X
FILTER BERM	** X	** X	X			
INLET PROTECTION	** X	** X	X		X	X
DEWATERING			X			X
SEDIMENT TRAP						X
NATURAL BUFFER ENCROACHMENT	* X	* X	* X		* X	* X
COMPOST SOCK	** X	** X	** X		X	X
OTHER:						
<b>RUN OFF CONTROL</b>						
CONSTRUCTION ENTRANCE	** X	X	X		X	X
PIPE SLOPE DRAIN						
OUTLET PROTECTION						
SURFACE ROUGHENING					X	
CHECK DAMS						
OTHER:						
<b>POLLUTION PREVENTION</b>						
PROPER SIGNAGE	X	X	X		X	X
HAZ WASTE MGMT	X	X	X			
SPILL KIT ON-SITE	X	X	X		X	X
CONCRETE WASHOUT AREA			X			
OTHER:						

- \* SIGNIFIES ADDITIONAL BMP'S REQUIRED FOR WORK WITHIN 50' OF WATER OF THE STATE.
- \*\* SIGNIFIES BMP THAT WILL BE INSTALLED PRIOR TO ANY GROUND DISTURBING ACTIVITY.

**RATIONALE STATEMENT**

A COMPREHENSIVE LIST OF AVAILABLE BEST MANAGEMENT PRACTICES (BMP) OPTIONS BASED ON DEQ'S GUIDANCE MANUAL HAS BEEN REVIEWED TO COMPLETE THIS EROSION AND SEDIMENT CONTROL PLAN. SOME OF THE ABOVE LISTED BMP'S WERE NOT CHOSEN BECAUSE THEY WERE DETERMINED TO NOT EFFECTIVELY MANAGE EROSION PREVENTION AND SEDIMENT CONTROL FOR THIS PROJECT BASED ON SPECIFIC SITE CONDITIONS, INCLUDING SOIL CONDITIONS TOPOGRAPHIC CONSTRAINTS, ACCESSIBILITY TO THE SITE, AND OTHER RELATED CONDITIONS, AS THE PROJECT PROGRESSES AND THERE IS A NEED TO REVISE THE ESC PLAN, AN ACTION PLAN WILL BE SUBMITTED.

INITIAL \_\_\_\_\_

**PERMITTEE'S SITE INSPECTOR:** ANDY STIRLING

COMPANY/AGENCY: CITY OF SHERWOOD

PHONE: (503) 925-2307

FAX: N/A

E-MAIL: stirlinga@sherwoodoregon.gov

DESCRIPTION OF EXPERIENCE: CESCL CERTIFICATION ID# ECO-3-6071946

EXPIRES 7/7/2022

**SHEET INDEX**  
**EROSION AND SEDIMENT CONTROL PLANS**

- ESC-1 EROSION AND SEDIMENT CONTROL COVER SHEET AND GENERAL NOTES
- ESC-2 EROSION AND SEDIMENT CONTROL PLAN - 1
- ESC-3 EROSION AND SEDIMENT CONTROL PLAN - 2
- ESC-4 EROSION AND SEDIMENT CONTROL DETAILS - 1
- ESC-5 EROSION AND SEDIMENT CONTROL DETAILS - 2
- ESC-6 DEWATERING PLAN
- ESC-7 DEWATERING DETAILS



G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-ESC-1.dwg ESC-1 1/21/2021 4:48 PM JUSTIN.DEUEL 23.0s (LMS Tech)

NO.	DATE	BY	REVISION

NOTICE

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU DESIGNED  
EJJ DRAWN  
BVO CHECKED



**EROSION AND SEDIMENT CONTROL  
COVER SHEET AND GENERAL NOTES**

PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021

SHEET

ESC-1


8 of 32



**LEGEND**

- DRAINAGE FLOW DIRECTION
- SEDIMENT FENCING
- COMPOST FILTER BERM
- CONSTRUCTION ENTRANCE
- INLET PROTECTION
- CONCRETE WASHOUT

- NOTES:**
1. ALL BASE ESC MEASURES (INLET PROTECTION, PERIMETER SEDIMENT CONTROL, GRAVEL CONSTRUCTION ENTRANCES, ETC.) MUST BE IN PLACE, FUNCTIONAL, AND APPROVED IN AN INITIAL INSPECTION, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.
  2. SEDIMENT BARRIERS APPROVED FOR USE INCLUDE SEDIMENT FENCE; BERMS CONSTRUCTED OUT OF MULCH, CHIPPINGS, OR OTHER SUITABLE MATERIAL; COMPOST SOCKS; STRAW WATTLES; OR OTHER APPROVED MATERIALS.
  3. SENSITIVE RESOURCES INCLUDING, BUT NOT LIMITED TO, TREES, WETLANDS, AND RIPARIAN PROTECTION AREAS SHALL BE CLEARLY DELINEATED WITH ORANGE CONSTRUCTION FENCING OR CHAIN LINK FENCING IN A MANNER THAT IS CLEARLY VISIBLE TO ANYONE IN THE AREA. NO ACTIVITIES ARE PERMITTED TO OCCUR BEYOND THE CONSTRUCTION BARRIER.
  4. CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES INCLUDING, BUT NOT LIMITED TO, TIRE WASHES AND DAILY STREET SWEEPING AND VACUUMING OF SW CENTURY DRIVE AND THE TEMPORARY ACCESS EASEMENT THROUGH BUSINESS PARK MAY BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.
  5. RUN-ON AND RUN-OFF CONTROLS SHALL BE IN PLACE AND FUNCTIONING PRIOR TO BEGINNING SUBSTANTIAL CONSTRUCTION ACTIVITIES. RUN-ON AND RUN-OFF CONTROL MEASURES INCLUDE SLOPE DRAINS (WITH OUTLET PROTECTION), CHECK DAMS, SURFACE ROUGHENING, AND BANK STABILIZATION.
  6. SEED USED FOR TEMPORARY OR PERMANENT SEEDING SHALL ADHERE TO THE SPECIFICATIONS, UNLESS OTHERWISE AUTHORIZED.
  7. STOCKPILED SOIL SHALL BE COVERED WITH PLASTIC SHEETING OR STRAW MULCH. SEDIMENT FENCE IS REQUIRED AROUND THE PERIMETER OF THE STOCKPILE.
  8. AREAS SUBJECT TO WIND EROSION SHALL USE APPROPRIATE DUST CONTROL MEASURES INCLUDING THE APPLICATION OF A FINE SPRAY OF WATER, PLASTIC SHEETING, STRAW MULCHING, OR OTHER APPROVED MEASURES.
  9. LIMIT SPEED OF VEHICLES ON SITE AND MOISTEN HAUL ROADS AS NECESSARY TO CONTROL DUST.
  10. ACTIVE INLETS TO STORM WATER SYSTEMS SHALL BE PROTECTED THROUGH THE USE OF APPROVED INLET PROTECTION MEASURES. ALL INLET PROTECTION MEASURES ARE TO BE REGULARLY INSPECTED AND MAINTAINED AS NEEDED.
  11. CONTRACTOR SHALL INSTALL INLET PROTECTION ON ALL INLETS WITHIN AREA OF PROJECT IMPROVEMENTS AS SHOWN ON SHEET ESC-2 AND ESC-3. ADDITIONAL INLETS NOT SHOWN ON THIS PLAN MAY BE PRESENT.
  12. VEGETATED CORRIDOR BOUNDARY IS NOT SHOWN FOR CLARITY WHERE IT SHARES A BOUNDARY WITH WETLAND AND/OR ROCK CREEK ORDINARY HIGH WATER MARK.
  13. HAZARDOUS MATERIAL CONTAINMENT MEASURES AND MACHINERY FUELING PROCEDURES TO BE IN ACCORDANCE WITH THE SPECIFICATIONS.



**PLAN**  
SCALE: 1"=40'

G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-ESC.dwg ESC-2 3/11/2021 8:34 AM JUSTIN.DEUEL 23.0s (LMS Tech)

NO.	DATE	BY	REVISION

**NOTICE**

0 1/2 1

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU DESIGNED  
EJJ DRAWN  
BVO CHECKED

**REGISTERED PROFESSIONAL ENGINEER**  
75681

*Brendan V. O'Sullivan*

OREGON  
JUNE 28, 2009

BRENDAN V. O'SULLIVAN  
RENEWS 12-31-22

**murraysmith**

**City of Sherwood Oregon**

**CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1**

**EROSION AND SEDIMENT CONTROL  
PLAN - 1**

PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021

SHEET

**ESC-2**


9 of 32

**LEGEND**

- DRAINAGE FLOW DIRECTION
- SEDIMENT FENCING
- COMPOST FILTER BERM
- CONSTRUCTION ENTRANCE
- INLET PROTECTION
- CONCRETE WASHOUT

**NOTES:**

1. ALL BASE ESC MEASURES (INLET PROTECTION, PERIMETER SEDIMENT CONTROL, GRAVEL CONSTRUCTION ENTRANCES, ETC.) MUST BE IN PLACE, FUNCTIONAL, AND APPROVED IN AN INITIAL INSPECTION, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.
2. SEDIMENT BARRIERS APPROVED FOR USE INCLUDE SEDIMENT FENCE; BERMS CONSTRUCTED OUT OF MULCH, CHIPPINGS, OR OTHER SUITABLE MATERIAL; COMPOST SOCKS; STRAW WATTLES; OR OTHER APPROVED MATERIALS.
3. SENSITIVE RESOURCES INCLUDING, BUT NOT LIMITED TO, TREES, WETLANDS, AND RIPARIAN PROTECTION AREAS SHALL BE CLEARLY DELINEATED WITH ORANGE CONSTRUCTION FENCING OR CHAIN LINK FENCING IN A MANNER THAT IS CLEARLY VISIBLE TO ANYONE IN THE AREA. NO ACTIVITIES ARE PERMITTED TO OCCUR BEYOND THE CONSTRUCTION BARRIER.
4. CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES INCLUDING, BUT NOT LIMITED TO, TIRE WASHES AND DAILY STREET SWEEPING AND VACUUMING OF SW CENTURY DRIVE AND THE TEMPORARY ACCESS EASEMENT THROUGH BUSINESS PARK MAY BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.
5. RUN-ON AND RUN-OFF CONTROLS SHALL BE IN PLACE AND FUNCTIONING PRIOR TO BEGINNING SUBSTANTIAL CONSTRUCTION ACTIVITIES. RUN-ON AND RUN-OFF CONTROL MEASURES INCLUDE SLOPE DRAINS (WITH OUTLET PROTECTION), CHECK DAMS, SURFACE ROUGHENING, AND BANK STABILIZATION.
6. SEED USED FOR TEMPORARY OR PERMANENT SEEDING SHALL ADHERE TO THE SPECIFICATIONS, UNLESS OTHERWISE AUTHORIZED.
7. STOCKPILED SOIL SHALL BE COVERED WITH PLASTIC SHEETING OR STRAW MULCH. SEDIMENT FENCE IS REQUIRED AROUND THE PERIMETER OF THE STOCKPILE.
8. AREAS SUBJECT TO WIND EROSION SHALL USE APPROPRIATE DUST CONTROL MEASURES INCLUDING THE APPLICATION OF A FINE SPRAY OF WATER, PLASTIC SHEETING, STRAW MULCHING, OR OTHER APPROVED MEASURES.
9. LIMIT SPEED OF VEHICLES ON SITE AND MOISTEN HAUL ROADS AS NECESSARY TO CONTROL DUST.
10. ACTIVE INLETS TO STORM WATER SYSTEMS SHALL BE PROTECTED THROUGH THE USE OF APPROVED INLET PROTECTION MEASURES. ALL INLET PROTECTION MEASURES ARE TO BE REGULARLY INSPECTED AND MAINTAINED AS NEEDED.
11. CONTRACTOR SHALL INSTALL INLET PROTECTION ON ALL INLETS WITHIN AREA OF PROJECT IMPROVEMENTS AS SHOWN ON SHEET ESC-2 AND ESC-3. ADDITIONAL INLETS NOT SHOWN ON THIS PLAN MAY BE PRESENT.
12. VEGETATED CORRIDOR BOUNDARY IS NOT SHOWN FOR CLARITY WHERE IT SHARES A BOUNDARY WITH WETLAND AND/OR ROCK CREEK ORDINARY HIGH WATER MARK.
13. HAZARDOUS MATERIAL CONTAINMENT MEASURES AND MACHINERY FUELING PROCEDURES TO BE IN ACCORDANCE WITH THE SPECIFICATIONS.



**PLAN**  
SCALE: 1"=40'

G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-ESC.dwg ESC-3 3/11/2021 8:34 AM JUSTIN.DEUEL 23.03 (LMS Tech)

NO.	DATE	BY	REVISION

**NOTICE**

0 1/2 1

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU DESIGNED  
EJJ DRAWN  
BVO CHECKED

REGISTERED PROFESSIONAL ENGINEER  
OREGON  
BRENDA V. O'SULLIVAN  
RENEWS 12-31-22

**murraysmith**

**CITY OF SHERWOOD**  
**ROCK CREEK**  
**SANITARY TRUNK LINE**  
**UPSIZING PROJECT -**  
**PHASE 1**

**EROSION AND SEDIMENT CONTROL**  
**PLAN - 2**









PROJECT NO.: 19-2481.402 | SCALE: AS SHOWN | DATE: FEBRUARY 2021

SHEET


**ESC-3**

10 of 32



G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-ESC.dwg ESC-4 3/11/2021 8:34 AM JUSTIN.DEUEL 23.0s (LMS Tech)



NO.	DATE	BY	REVISION



JJU  
DESIGNED  
EJJ  
DRAWN  
BVO  
CHECKED









**EROSION AND SEDIMENT CONTROL  
DETAILS - 1**

PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021

SHEET  
**ESC-4**  
11 of 32

G:\PD\Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-ESC.dwg ESC-5 3/11/2021 8:34 AM JUSTIN.DEUEL 23.0s (LMS Tech)



FOR FURTHER INFORMATION ON DESIGN CRITERIA SEE CHAPTER 4 OF CLEAN WATER SERVICES EROSION PREVENTION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL.

SPACING FOR CHECK DAMS

DITCH GRADE	6 INCH	12 INCH	18 INCH
6%	NOT ALLOWED	16 FT O.C.	26 FT O.C.
5%	NOT ALLOWED	20 FT	30 FT
4%	NOT ALLOWED	26 FT	40 FT
3%	15 FT	33 FT	50 FT
2%	25 FT	50 FT	80 FT

BARRIER SPACING FOR GENERAL APPLICATION

INSTALL PARALLEL ALONG CONTOURS AS FOLLOWS

% SLOPE	SLOPE H:V	MAXIMUM SPACING ON SLOPE
10% OR FLATTER	10:1 OR FLATTER	300 FT
>10% OR <15%	>10:1 OR <7.5:1	150 FT
>15% OR <20%	>7.5:1 OR <5:1	100 FT
>20% OR <30%	>5:1 OR <3.5:1	50 FT
>30% OR <50%	>3.5:1 OR <2:1	25 FT


NOTE:

- FOR MORE INFORMATION REGARDING THESE TABLES SEE CHAPTER 4 OF CLEAN WATER SERVICES EROSION PREVENTION AND SEDIMENT CONTROL DESIGN MANUAL.


SPACING TABLES

CleanWater Services

DRAWING NO. 940 REVISED 10-31-19



NO.	DATE	BY	REVISION



JJU  
DESIGNED  
EJJ  
DRAWN  
BVO  
CHECKED




CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1

EROSION AND SEDIMENT CONTROL  
DETAILS - 2

PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021

SHEET  
ESC-5  
12 of 32

G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-ESC-6.dwg ESC-6 3/11/2021 8:05 AM JUSTIN.DEUEL 23.0s (LMS Tech)



**PLAN**  
SCALE: 1"=20'

**NOTES:**

1. ALL WORK PERFORMED WITHIN EXTENTS OF ROCK CREEK ORDINARY HIGH WATER MARK TO BE COMPLETED WITHOUT THE USE OF MECHANICAL MEANS.
2. ALL TREES SHOWN IN PLAN TO BE PROTECTED IN PLACE. SEE SHEETS C-1 AND C-2 FOR TREE PROTECTION AND REMOVAL PLAN.
3. LOCATIONS OF DEWATERING WELLS SHOWN ARE APPROXIMATE. CONTRACTOR TO DECOMMISSION ALL DEWATERING WELLS IN ACCORDANCE WITH ALL STATE OF OREGON LAWS AND REGULATIONS, SEE SPECIFICATIONS.
4. TURBIDITY MONITORING SHALL BE CONDUCTED AND RECORDED DURING IN-WATER WORK PER NATIONWIDE SECTION 401 WATER QUALITY CERTIFICATION (401 WQC) 2013-128-1, SEE SPECIFICATIONS.
5. ALL DEWATERING WORK SHALL BE PERFORMED IN ACCORDANCE WITH JURISDICTIONAL AGENCY REQUIREMENTS, SEE SPECIFICATIONS.
6. EROSION AND SEDIMENT CONTROL BMPs NOT SHOWN FOR CLARITY, SEE SHEET ESC-2 AND ESC-3.

NO.	DATE	BY	REVISION

NOTICE  
0 1/2 1  
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU DESIGNED  
EJJ DRAWN  
BVO CHECKED




**CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1**

**DEWATERING PLAN**  
PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021

SHEET  
**ESC-6**  
13 of 32


G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-ESC-6.dwg ESC-7 3/11/2021 8:05 AM JUSTIN.DEUEL 23.0s (LMS Tech)



**NOTES:**

1. LOCATIONS, DIMENSIONS AND DETAILS OF DEWATERING WELLS ARE APPROXIMATE AND SCHEMATIC IN NATURE. CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, INSTALLATION, OPERATION AND MAINTENANCE OF THE DEWATERING SYSTEM, SEE SPECIFICATIONS FOR REQUIREMENTS.


**DEWATERING WELL DETAIL**  
SCALE: NTS



NO.	DATE	BY	REVISION

NOTICE  
0 1/2 1  
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU  
DESIGNED  
EJJ  
DRAWN  
BVO  
CHECKED






**CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1**

<b>DEWATERING DETAILS</b>			
PROJECT NO.:	19-2481.402	SCALE:	AS SHOWN
DATE:	FEBRUARY 2021		


SHEET  
**ESC-7**  
14 of 32

**LEGEND**

-  REMOVE TREE
-  TREE PROTECTION FENCING
-  TEMP AC OVERLAY

**NOTES:**

1. TREE PROTECTION FENCING SHALL BE PLACED AT OR OUTSIDE OF DRIPLINE.
2. INSTALL ORANGE NO WORK FENCE AT EASEMENT AND CONSTRUCTION LIMITS PER DETAIL 1, SHEET ESC-5, TYPICAL.
3. TREE TRUNK DIAMETER MEASURED AT BREAST HEIGHT. TREE REMOVAL SCHEDULE ENTRIES WITH MULTIPLE DIAMETERS LISTED DENOTE TREES WITH MULTIPLE TRUNKS.
4. STAGING OF MATERIALS, EQUIPMENT AND STOCKPILING OF NATIVE AND IMPORTED FILL SHALL NOT BE ALLOWABLE WITHIN THE TEMPORARY CONSTRUCTION AREA ON THE DEPARTMENT OF THE INTERIOR PROPERTY.
5. TAPER THICKNESS OF OVERLAY NEAR AT GRADE APPURTENANCES TO MAINTAIN ACCESS DURING CONSTRUCTION. SEE SHEET C-12 FOR DETAILS.
6. TAPER THICKNESS OF OVERLAY AS REQUIRED TO COMPLY WITH ADA REQUIREMENTS. SEE SHEET C-12 FOR DETAILS.
7. SEE SPECIFICATIONS FOR REQUIREMENTS WITHIN TEMPORARY ACCESS EASEMENT.
8. CONTRACTOR TO PROTECT EXISTING CONCRETE CURB. CURB DAMAGED DURING CONSTRUCTION SHALL BE REPLACED BY CONTRACTOR AT NO COST TO OWNER.



**TREE REMOVAL SCHEDULE**

TREE TYPE	QUANTITY (EA)	TREE TRUNK DIA (IN), SEE NOTE 3
DECIDUOUS	7	6
DECIDUOUS	1	6 / 6
DECIDUOUS	1	6.5
DECIDUOUS	2	7
DECIDUOUS	1	9.5
DECIDUOUS	1	11
DECIDUOUS	1	12
DECIDUOUS	1	15 / 16
DECIDUOUS	1	17

**PLAN**  
SCALE: 1"=40'

G:\PD\Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-C-dwg C-1 3/10/2021 3:47 PM JUSTIN.DEUEL 23.0s (LMS Tech)

NO.	DATE	BY	REVISION

**NOTICE**  
0 1/2 1  
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU DESIGNED  
EJJ DRAWN  
BVO CHECKED

**REGISTERED PROFESSIONAL ENGINEER**  
OREGON  
75681  
Brendan V. O'Sullivan  
RENEWS 12-31-22

**murraysmith**

**City of Sherwood Oregon**



**CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1**

**SITE ACCESS, TREE PROTECTION  
AND REMOVAL PLAN - 1**

PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021


SHEET  
**C-1**  
15 of 32

**LEGEND**

-  REMOVE TREE
-  TREE PROTECTION FENCING

**NOTES:**

1. TREE PROTECTION FENCING SHALL BE PLACED AT OR OUTSIDE OF DRIPLINE.
2. INSTALL ORANGE NO WORK FENCE AT EASEMENT AND CONSTRUCTION LIMITS PER DETAIL 1, SHEET ESC-5, TYPICAL.




**PLAN**  
SCALE: 1"=40'

G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-C.dwg C-2 3/10/2021 3:47 PM JUSTIN.DEUEL 23.0s (LMS Tech)


NO.	DATE	BY	REVISION

**NOTICE**




IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU  
DESIGNED  
EJJ  
DRAWN  
BVO  
CHECKED



RENEWS 12-31-22

**CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1**



**SITE ACCESS, TREE PROTECTION  
AND REMOVAL PLAN - 2**

PROJECT NO.: 19-2481.402    SCALE: AS SHOWN    DATE: FEBRUARY 2021



G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-C.dwg C-3 3/10/2021 3:47 PM JUSTIN.DEUEL 23.0s (LMS Tech)


2S129A-00100  
 UNITED STATES OF AMERICA  
 DEPT OF THE INTERIOR  
 FISH & WILDLIFE SERVICE  
 20555 SW GERDA LANE



NO.	DATE	BY	REVISION

NOTICE  
 0 1/2 1  
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU DESIGNED  
 EJJ DRAWN  
 BVO CHECKED




CITY OF SHERWOOD  
 ROCK CREEK  
 SANITARY TRUNK LINE  
 UPSIZING PROJECT -  
 PHASE 1


PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021

SHEET  
 C-3  
 17 of 32

G:\PD\Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-C.dwg C-4 3/10/2021 3:47 PM JUSTIN.DEUEL 23.0s (LMS Tech)



**PLAN**  
SCALE: 1"=20'



**PROFILE**  
SCALE: 1"=20' HORIZ, 1"=5' VERT

NO.	DATE	BY	REVISION

**NOTICE**  
0 1/2 1  
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU DESIGNED  
EJJ DRAWN  
BVO CHECKED





**CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1**

**SEWER PLAN AND PROFILE  
STA 5+00 TO STA 10+00**

PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021

SHEET  
**C-4**  
18 of 32


G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-C.dwg C-5 3/10/2021 3:47 PM JUSTIN.DEUEL 23.0s (LMS Tech)



NO.	DATE	BY	REVISION

NOTICE  
 0 1/2 1  
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU DESIGNED  
 EJJ DRAWN  
 BVO CHECKED







**SEWER PLAN AND PROFILE  
 STA 10+00 TO STA 14+54**

PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021

SHEET  
**C-5**  
 19 of 32

G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-C.dwg C-6 3/10/2021 3:47 PM JUSTIN.DEUEL 23.0s (LMS Tech)





- CASING NOTES:**
1. ANNULAR SPACE BETWEEN 18" DIAMETER RCP AND 12" DIAMETER PVC CARRIER PIPE TO BE FILLED WITH SAND PER SPECIFICATIONS. CONTRACTOR TO INSTALL MINIMUM 12" THICK NON-SHRINK GROUT BULK HEAD AT EACH END OF 18" DIAMETER CASING TO PREVENT SAND MIGRATION.
  2. PROVIDE 2" MINIMUM CLEARANCE BETWEEN CASING AND CARRIER PIPE BELLS AND APPURTENANCES.
  3. CONTRACTOR TO VERIFY CASING SIZES PRIOR TO SIZING AND ORDERING CASING INSULATORS. CUSTOM CASING INSULATORS WILL BE REQUIRED TO ACHIEVE SPECIFIED GRADE, SEE SPECIFICATIONS.
  4. MANHOLE BENCH AND CHANNEL TO BE CONSTRUCTED FOR NEW SEWER INVERT ELEVATIONS, SEE DETS, SHT C-12.
  5. INSTALL 3/4"-0 CRUSHED ROCK WITHIN PIPE ZONE BETWEEN BULKHEAD AND MANHOLE WALL.

NO.	DATE	BY	REVISION

**NOTICE**  
0 1/2 1  
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE


JJU DESIGNED  
EJJ DRAWN  
BVO CHECKED



**SEWER PLAN AND PROFILE  
STA A1+00 TO STA A2+18  
AND SLIPLINE DETAIL**

PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021


C:\Users\Lita\Box\Jobs\5993.0 Rock Creek Sanitary Trunk Line Upsizing Project - Phase 1\CADD\19-2481-OR-C7\_McMJAC.dwg C-7 2/12/2021 4:57 PM LITA 23.1s (LMS Tech)



**CROSSING PLAN STA 7+40 TO 10+00**  
SCALE: 1"=20'

**NOTES:**

1. CONTRACTOR TO DETERMINE SIZE AND CONFIGURATION OF LAUNCH AND RECEIVING PITS BASED ON SELECTED MEANS AND METHODS FOR CONSTRUCTION.
2. COORDINATE RECEIVING PIT EXCAVATION WITH IMPROVEMENTS TO EXISTING OUTFALL. EXTEND OR RELOCATE THE EXISTING 20" CONCRETE SD OUTFALL PIPING TEMPORARILY OR PROVIDE MEASURES TO PREVENT FLOW FROM EXISTING OUTFALL PIPING FLOWING INTO RECEIVING PIT DURING CONSTRUCTION AS NECESSARY.



**CROSSING PROFILE STA 7+40 TO 10+00**  
SCALE: 1"=20' HORIZ, 1"=5' VERT



NO.	DATE	BY	REVISION

NOTICE  
0 1/2 1  
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED  
CAD  
DRAWN  
CHECKED



**CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1**

**SW TUALATIN-SHERWOOD RD  
TRENCHLESS CROSSING  
PLAN AND PROFILE**




PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2020

SHEET


C-7

21 of 32


C:\Users\Lita\Box\Jobs\5993.0 Rock Creek Sanitary Trunk Line Upsizing Project - Phase 1\CADD\19-2481-OR-C8\_McMJAC.dwg C-8 3/10/2021 9:55 AM LITA 23.1s (LMS Tech)



- STEEL CASING AND GROUT PORT NOTES:**
1. STEEL CASING SHALL HAVE A MINIMUM WALL THICKNESS OF 0.5". MINIMUM CASING PIPE THICKNESS HAS BEEN SIZED FOR ANTICIPATED EARTH PRESSURES AND LIVE LOADS. CONTRACTOR IS RESPONSIBLE FOR INCREASING THE THICKNESS FOR INSTALLATION LOADS AS NECESSARY BASED ON THE CONTRACTOR'S SELECTED MEANS AND METHODS.
  2. THE DIAMETER OF THE STEEL CASING SHALL BE MINIMUM 48" IN ORDER TO ALLOW FOR PERSONNEL ACCESS TO BREAK UP AND REMOVE BOULDERS. CONTRACTOR SHALL UPSIZE CASING AS NECESSARY BASED ON SELECTED MEANS AND METHODS.
  3. SEE SPECIAL PROVISION S-52 FOR STEEL CASING PIPE REQUIREMENTS.
  4. SEE SPECIAL PROVISION S-52 FOR TRENCHLESS INSTALLATION REQUIREMENTS.
  5. MINIMUM ANNULAR CLEARANCE BETWEEN CASING AND SEWER PIPE SHALL BE 4" AND FILLED WITH SAND. CONTRACTOR TO INSTALL NON-SHRINK GROUT BULKHEAD AT EACH END OF CASING TO PREVENT SAND MIGRATION AND TO PREVENT GROUNDWATER FROM ENTERING CASING. SEE PIPE SEAL DETAIL (DRAWING NO. 610) ON SHEET C-13.
  6. PROVIDE ONE SET OF 3 GROUT PORTS PER CASING SECTION OR 10' ON CENTER WHICHEVER RESULTS IN A CLOSER SPACING.
  7. GROUT ANNULAR SPACE OUTSIDE CASING PER REQUIREMENTS IN SPECIAL PROVISION S-52.
  8. CASING SPACERS SHALL BE ADJUSTABLE TO ALLOW SEWER PIPE TO BE INSTALLED AT THE REQUIRED LINE AND GRADE WHILE MAINTAINING MINIMUM BACKFILL REQUIREMENTS.




**GROUT PORT SPACING DETAIL**  
SCALE: NTS



**SCP WITH SURFACE MONUMENT**  
SCALE: NTS

- SETTLEMENT CONTROL POINT NOTES:**
1. INSTRUMENTATION INSTALLATION METHODS, EQUIPMENT, MATERIALS, TIMING, TOLERANCES AND INSTRUMENTATION MONITORING, AND THE REPORTING RESULTS SHALL COMPLY WITH THE REQUIREMENTS OF SPECIAL PROVISION S-52.
  2. MONITORING OF THE SETTLEMENT CONTROL POINTS SHALL BE CONTINUED AT LEAST 2 WEEKS AFTER THE CASING INSTALLATION. THEN THE SETTLEMENT CONTROL POINTS SHALL BE REMOVED AND BACKFILLED TO RESTORE THE ORIGINAL SURFACE CONDITION.
  3. ADJUST INSTRUMENT AND MONITORING LOCATIONS AS APPROVED OR DIRECTED BY THE OWNER'S REPRESENTATIVE TO AVOID EXISTING UTILITIES AND MINIMIZE CONFLICTS WITH CONSTRUCTION OPERATIONS.
  4. PRIOR TO CONSTRUCTION, OBTAIN PERMITS AND COMPLY WITH REQUIREMENTS OF THE AGENCIES, OWNERS, UTILITIES, AND OTHER ENTITIES WITH JURISDICTION OVER ACCESS AND INSTALLATION OF THE INSTRUMENTATION.



**SETTLEMENT CONTROL POINT (SCP) DETAIL**  
SCALE: NTS



NO.	DATE	BY	REVISION

**NOTICE**  
0 1/2 1  
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED  
CAD  
DRAWN  
CHECKED




**CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1**


**TRENCHLESS & SETTLEMENT  
INSTRUMENTATION  
SECTIONS & DETAILS**

PROJECT NO.: 19-2481.402 SCALE: NOT TO SCALE DATE: FEBRUARY 2020


C:\Users\Lita\Box\Jobs\5993.0 Rock Creek Sanitary Trunk Line Upsizing Project - Phase 1\CADD\19-2481-OR-C9\_McMJAC.dwg C-9 2/12/2021 4:56 PM LITA 23.1s (LMS Tech)




**PASSIVE PRESSURE**




**ACTIVE EARTH PRESSURE FOR CANTILEVER WALLS (NOTE 2)**




**APPARENT EARTH PRESSURE FOR BRACED WALLS (NOTE 2)**



**HYDROSTATIC PRESSURE**




**TEMPORARY SURCHARGE PRESSURE (NOTE 3)**



**ROADWAY EMBANKMENT SURCHARGE PRESSURE (NOTE 4)**

**LATERAL EARTH PRESSURES FOR TEMPORARY EXCAVATION SHORING**

SCALE: NTS



**NOTES:**

1. THE ACTIVE AND APPARENT EARTH PRESSURES ARE THE MINIMUM TO BE USED FOR DESIGN OF THE TRENCHLESS CROSSING LAUNCHING AND RECEIVING SHAFTS EXCAVATION SUPPORT SYSTEM. THE LOADS DO NOT INCLUDE ANY FACTOR OF SAFETY THAT MUST BE APPLIED IN THE EXCAVATION SYSTEM DESIGN. CONTRACTOR IS RESPONSIBLE FOR EVALUATING ACTUAL LOADS, BUT IN NO CASE SHALL BE LESS THAN THOSE SHOWN.
2. DEPENDING ON SUPPORT OF EXCAVATION DESIGN, USE EITHER ACTIVE OR APPARENT EARTH PRESSURE. USING BOTH SIMULTANEOUSLY IS NOT REQUIRED.
3. THE TEMPORARY SURCHARGE LOAD SHOWN IS THE MINIMUM REQUIRED. CONTRACTOR SHALL DEVELOP SPECIFIC SURCHARGE PRESSURES BASED ON ACTUAL EQUIPMENT USED.
4. SHORING SIDE IMMEDIATELY ADJACENT TO THE ROAD EMBANKMENT SHALL BE DESIGNED TO CONSIDER EMBANKMENT SURCHARGE LOAD.
5. SEE SPECIAL PROVISION S-51 FOR SHAFT DESIGN & CONSTRUCTION REQUIREMENTS.

**LEGEND:**

- H HEIGHT OF EXCAVATION (TEMPORARY) IN FEET
- H<sub>w</sub> DISTANCE FROM BASE OF EXCAVATION TO WATER LEVEL
- D DEPTH OF EMBEDMENT
- H<sub>e</sub> HEIGHT OF EMBANKMENT



NO.	DATE	BY	REVISION

NOTICE  
  
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

DESIGNED  
 CAD  
 DRAWN  
 CHECKED




CITY OF SHERWOOD  
 ROCK CREEK  
 SANITARY TRUNK LINE  
 UPSIZING PROJECT -  
 PHASE 1

**EARTH PRESSURE DIAGRAM**

PROJECT NO.: 19-2481.402 SCALE: NOT TO SCALE DATE: FEBRUARY 2020

G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-C DETS.dwg C-10 3/11/2021 9:33 AM JUSTIN.DEUEL 23.0s (LMS Tech)



STORMWATER OUTFALL  
PLAN, SEE DET 1, SHT C-11

CLASS 200 RIPRAP

SEE SHTS C-4 AND C-5 FOR  
SEWER PLAN AND PROFILE

50' PERM  
SEWER ESMT

80' TEMP  
CONST ESMT

PLAN  
SCALE: 1"=10'

NOTES:  
1. INSTALL JUTE MATTING ON DISTURBED SLOPES  
GREATER THAN 2H:1V.

NO.	DATE	BY	REVISION

NOTICE  
0 1/2 1  
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU  
DESIGNED  
EJJ  
DRAWN  
BVO  
CHECKED




CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1

**SITE GRADING PLAN**  
PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021


SHEET  
C-10  
24 of 32




G:\PD\Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-C DETS.dwg C-11 3/11/2021 9:33 AM JUSTIN.DEUEL 23.0s (LMS Tech)



**OUTFALL PLAN** 1  
SCALE: 1"=5' C-10




**OUTFALL SECTION** A  
SCALE: NTS



1. BEDDING AND PIPE ZONE MATERIAL SHALL BE COMPACTED TO 90% OF THE MODIFIED PROCTOR DRY DENSITY VALUE (ASTM D1557). COMPACTION OF BEDDING MATERIAL SHALL BE ACCOMPLISHED WITHOUT VIBRATORY COMPACTION METHODS.
2. THE TRENCH WIDTH AT THE SURFACE OF THE GROUND SHALL BE KEPT TO A MINIMUM NECESSARY TO INSTALL THE PIPE IN A SAFE MANNER.
3. THE MINIMUM TRENCH WIDTH IN THE PIPE ZONE SHALL PROVIDE A CLEAR WORKING SPACE OF SIX INCHES OUTSIDE THE MAXIMUM OUTSIDE DIAMETER OF THE PIPE BEING INSTALLED.
4. IN ALL CASES, TRENCHES SHALL BE OF SUFFICIENT WIDTH TO ALLOW FOR SHORING, PROPER JOINING OF PIPE, AND BACKFILLING OF MATERIAL ALONG THE SIDES OF THE PIPE.
5. HIGH STRENGTH WOVEN FILTER FABRIC SHALL BE MIRAFI RS280i OR APPROVED EQUAL.
6. SEE STANDARD DRAWING 590 FOR COMPACTION AND SURFACE RESTORATION REQUIREMENTS.

**TRENCH WITH SUBGRADE STABILIZATION** 2  
SCALE: NTS



- NOTES:
1. CONSTRUCT TRENCH DAMS WITH BENTONITE, DO NOT USE TOPSOIL FOR FILLING BENTONITE.
  2. TRENCH DAMS SHALL BE INSTALLED IN PIPELINE TRENCH. APPROX LOCATION OF TRENCH DAMS ARE SHOWN ON PLAN SHEETS. COORDINATE EXACT LOCATION W/ FIELD ENGINEER.

**TYPICAL TRENCH DAM** 3  
SCALE: NTS

NO.	DATE	BY	REVISION

NOTICE  
0 1/2 1  
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU DESIGNED  
EJJ DRAWN  
BVO CHECKED




**CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1**

**CIVIL DETAILS - 1**

SHEET  
C-11  
25 of 32

PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021


G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-C DETS.dwg C-12 3/11/2021 9:33 AM JUSTIN.DEUEL 23.0s (LMS Tech)



**NOTES:**  
 1. EXISTING MANHOLE CORING FOR 18" SEWER LINE TO BE RE-CORED FOR 24" SEWER LINE CONNECTION TO CWS MH 829081. CONTRACTOR TO INSTALL BYPASS PIPING AS REQUIRED TO FACILITATE CONNECTION.

**EXISTING CWS MH 829081 RECHANNELIZATION** 1


SCALE: NTS



**NOTES:**  
 1. DRILL INTO MH WALL AND INSTALL #3 BARS AT 6" OC EACH WAY W/ HILTI HIT-RE-500-SD EPOXY, MINIMUM 4" EMBED. PROVIDE MINIMUM 12" LAP SPLICE.

**EXISTING COS MH 398NSAN RECHANNELIZATION** 2

SCALE: NTS




**NOTES:**  
 1. DRILL INTO MH WALL AND INSTALL #3 BARS AT 6" OC EACH WAY W/ HILTI HIT-RE-500-SD EPOXY, MINIMUM 4" EMBED. PROVIDE MINIMUM 12" LAP SPLICE.


**EXISTING COS MH 401NSAN RECHANNELIZATION** 3

SCALE: NTS

**NOTES:**  
 1. EXISTING PAVEMENT SHALL BE CLEANED AND FULL WIDTH OF ROADWAY SHALL BE TACKED PRIOR TO INSTALLATION OF GEOTEXTILE. INSTALL GEOTEXTILE ACCORDING TO MANUFACTURER INSTALLATION GUIDELINES.  
 2. TAPER OVERLAY THICKNESS FOR TIE-INS TO EXISTING CONCRETE DRIVEWAYS, AT-GRADE APPURTENANCES, PAVEMENT WHERE EXISTING CURB IS NOT PRESENT AND CROSSWALKS TO COMPLY WITH ADA REQUIREMENTS.  
 3. MATCH EXISTING SLOPE OF PAVEMENT. CONSIDER EXISTING DRAINAGE PATTERNS WHEN FEATHERING OVERLAY SURFACE TO MATCH EXISTING PAVEMENT SURFACE.



**SECTION A**  
 SCALE: NTS




**SECTION B**  
 SCALE: NTS

**NOTES:**  
 1. EXISTING PAVEMENT SHALL BE CLEANED AND FULL WIDTH OF ROADWAY SHALL BE TACKED PRIOR TO INSTALLATION OF GEOTEXTILE. INSTALL GEOTEXTILE ACCORDING TO MANUFACTURER INSTALLATION GUIDELINES.  
 2. TAPER OVERLAY THICKNESS FOR TIE-INS TO EXISTING CONCRETE DRIVEWAYS, AT-GRADE APPURTENANCES, AND CROSSWALKS TO COMPLY WITH ADA REQUIREMENTS.

NO.	DATE	BY	REVISION

**NOTICE**  
 0 1/2 1  
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU DESIGNED  
 EJJ DRAWN  
 BVO CHECKED



**murraysmith**



**CITY OF SHERWOOD  
 ROCK CREEK  
 SANITARY TRUNK LINE  
 UPSIZING PROJECT -  
 PHASE 1**

**CIVIL DETAILS - 2**









SHEET

C-12

26 of 32

PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021

G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-C DETS.dwg C-13 3/11/2021 9:33 AM JUSTIN.DEUEL 23.0s (LMS Tech)



NO.	DATE	BY	REVISION

**NOTICE**

0 1/2 1

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU DESIGNED  
EJJ DRAWN  
BVO CHECKED

**REGISTERED PROFESSIONAL ENGINEER**  
75681  
OREGON  
JUNE 28, 2009  
ALEXANDER V. OSULLIVAN  
RENEWS 12-31-22

**murraysmith**

**CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1**

**CLEAN WATER SERVICES  
STANDARD DETAILS - 1**

PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021

SHEET  
**C-13**  
27 of 32

G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-C DETS.dwg C-14 3/11/2021 9:33 AM JUSTIN.DEUEL 23.0s (LMS Tech)

**LARGE PRECAST CONCRETE MANHOLE - BASES**

Drawing No. 170 REVISED 10-31-19

CleanWater Services

**LARGE PRECAST CONCRETE MANHOLE - TYPES**

Drawing No. 180 REVISED 10-31-19

CleanWater Services

SIZE	60"	72"	84"	96"					
Type	Depth*	0'-15"	15'-30"	0'-15"	15'-30"	0'-15"	15'-30"	0'-15"	15'-30"
1	D Bars	#3 @ 12"	#3 @ 12"	#3 @ 12"	#4 @ 10"	#3 @ 10"	#4 @ 11"	#3 @ 9"	#4 @ 11"
	E Bars	#4 @ 12"	#4 @ 9"	#4 @ 9"	#4 @ 6"	#4 @ 8"	#5 @ 9"	#4 @ 7"	#5 @ 8"
2	E Bars	#4 @ 12"	#4 @ 8"	#4 @ 8"	#5 @ 8"	#4 @ 7"	#5 @ 7"	#4 @ 5"	#5 @ 6"
	I Bars	#4 @ 12"	#4 @ 9"	#4 @ 9"	#4 @ 6"	#4 @ 8"	#5 @ 9"	#4 @ 7"	#5 @ 8"
3	D Bars	#3 @ 12"	#3 @ 12"	#3 @ 12"	#4 @ 10"	#3 @ 10"	#4 @ 11"	#3 @ 9"	#4 @ 11"
	E Bars	#4 @ 12"	#4 @ 9"	#4 @ 9"	#4 @ 6"	#4 @ 8"	#5 @ 9"	#4 @ 7"	#5 @ 8"
4	E Bars	#4 @ 12"	#4 @ 9"	#4 @ 9"	#4 @ 6"	#4 @ 8"	#5 @ 9"	#4 @ 7"	#5 @ 8"
	F Bars	#4 @ 12"	#4 @ 9"	#4 @ 9"	#4 @ 6"	#4 @ 8"	#5 @ 9"	#4 @ 7"	#5 @ 8"

**LARGE PRECAST CONCRETE MANHOLE - LONG BASE SECTION REINF.**

Drawing No. 200 REVISED 10-31-19

CleanWater Services

**LARGE PRECAST CONCRETE MANHOLE TOP SLABS**

Drawing No. 220 REVISED 10-31-19

CleanWater Services

COVER DEPTH	6" to 12"	4'-0" to 7'-0"	7'-1" to 22'-0"
Size	T	"A" Bars "B" Bars	T "A" Bars "B" Bars T "A" Bars "B" Bars
60"	8"	No.5 @ 7 1/2" No.5 @ 7 1/2" 12"	No.5 @ 9" No.5 @ 9" 12" No.5 @ 9" No.5 @ 9"
72"	10"	No.5 @ 7" No.5 @ 7" 12"	No.5 @ 9" No.5 @ 9" 12" No.5 @ 7" No.5 @ 7"
84"	11"	No.5 @ 7" No.5 @ 7" 12"	No.5 @ 6" No.5 @ 6" 12" No.6 @ 6" No.5 @ 7"
96"	12"	No.5 @ 6" No.5 @ 6" 12"	No.5 @ 6" No.5 @ 6" 14" No.6 @ 6" No.5 @ 6"
108"	N/A	N/A N/A 12"	No.6 @ 8" No.6 @ 8" 16" No.7 @ 9" No.7 @ 9"
120"	N/A	N/A N/A 12"	No.6 @ 7" No.6 @ 7" 16" No.7 @ 8" No.7 @ 8"

**CONCRETE CAP**

Drawing No. 550 REVISED 10-31-19

CleanWater Services

**TRENCH BACKFILL DETAILS**

Drawing No. 590 REVISED 10-31-19

CleanWater Services

**RIP RAP DETAILS**

Drawing No. 790 REVISED 10-31-19

CleanWater Services

CLASS	CLASS	CLASS	CLASS	CLASS	PERCENT (BY WEIGHT)
50	100	200	700	2000	
					WEIGHT OF ROCK (LBS)
50-30	100-60	200-140	700-500	2000-1400	20
30-15	60-25	140-80	500-200	1400-700	30
15-2	25-2	80-8	200-20	700-40	40
2-0	2-0	8-0	20-0	40-0	10

**VEGETATED CORRIDOR SIGNAGE**

Drawing No. 794 REVISED 10-31-19

CleanWater Services



NO.	DATE	BY	REVISION

**NOTICE**

0 1/2 1

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE


JJU DESIGNED  
EJJ DRAWN  
BVO CHECKED



**CLEAN WATER SERVICES STANDARD DETAILS - 2**

PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021

G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-L.dwg L-1 3/11/2021 9:42 AM JUSTIN DEUEL 23.0s (LMS Tech)



**NOTES:**

1. ALL SHRUBS SHALL BE 1 GALLON WITH 1.5' MINIMUM HEIGHT AT TIME OF PLANTING. ALL TREES SHALL BE 2 GALLON WITH 2' MINIMUM HEIGHT AT TIME OF PLANTING. SEE DETAIL 5, SHEET L-4 FOR PLANTING PATTERN.
2. PROVIDE MINIMUM 10' CLEAR SPACE FROM ALL TREE PLANTINGS TO PROPOSED SANITARY SEWER INFRASTRUCTURE.
3. RESTORE EXISTING STORMWATER SWALE TO PRE-CONSTRUCTION GRADE. SEE SHEET C-4 FOR EXISTING STORMWATER SWALE INFRASTRUCTURE TO REMAIN.
4. REMOVE EXISTING WEEDS AND INVASIVE SPECIES FROM RESTORATION EXTENTS PRIOR TO BEGINNING SITE RESTORATION AND PLANTING.
5. FINAL LOCATIONS OF VEGETATED CORRIDOR SIGNAGE TO BE COORDINATED WITH AND DETERMINED BY ENGINEER.
6. ALL EXISTING TREES SHOWN ON THIS SHEET ARE TO BE PRESERVED DURING CONSTRUCTION. SEE SHEET C-1 FOR TREE PROTECTION AND REMOVAL REQUIREMENTS.

**SEED MIXES LEGEND**

SEED MIX	COMMON NAME (BOTANICAL NAME)	QUANTITY (LBS/ACRE)	QUANTITY (LBS SEEDS/ LBS SEED MIX)
WETLAND	TUFTED HAIRGRASS (DESCHAMPSIA CESPITOSA)	1.67	0.29
	SLENDER HAIRGRASS (DESCHAMPSIA ELONGATA)	1.00	0.18
	SLENDER RUSH (JUNCUS TENUIS)	1.39	0.24
	SPIKE BENTGRASS (AGROSTIC EXARATA)	1.67	0.29
UPLAND	WESTERN YARROW (ACHILLEA MILLEFOLIUM)	0.47	0.02
	CALIFORNIA OATGRASS (DANTHONIA CALIFORNICA)	4.65	0.18
	BLUE WILDRYE (ELYMUS GLAUCUS)	9.30	0.38
	MEADOW BARLEY (HORDEUM BRACHYANTHERUM)	9.30	0.38
	MEADOW CHECKERBLOOM (SIDALCEA CAMPESTRIS)	0.93	0.04

**PLANTING ZONES LEGEND**

PLANTING ZONE	AREA (ACRES)	SYMBOL
A	0.514	[Symbol]
B1	0.159	[Symbol]
B2	0.083	[Symbol]
C	0.070	[Symbol]
D1	0.397	[Symbol]
D2	0.305	[Symbol]
E	0.634	[Symbol]

**PLANTING SCHEDULE**

PLANTING ZONE	SEED MIX (LBS)	QUANTITY															
		SHRUB (EA), SEE NOTE 1												TREE (EA), SEE NOTE 1			
		WETLAND	UPLAND	DOUGLAS SPIRAEA (SPIRAEA DOUGLASII)	RED OSIER DOGWOOD (CORNUS ALBA)	PACIFIC NINEBARK (PHYSOCARPUS CAPITATUS)	OCEANSPRAY (HOLODISCUS DISCOLOR)	BLACK TWINBERRY (LONICERA INVOLUCRATA)	NOOTKA ROSE (ROSA NUTKANA)	RED ELDERBERRY (SAMBUCUS RACEMOSA)	SNOWBERRY (SYMPHORICARPOS ALBUS)	OREGON ASH (FRAXINUS LATIFOLIA)	BLACK HAWTHORN (CRATAEGUS DOUGLASII)	PACIFIC WILLOW (SALIX LUCIDA)	RED ALDER (ALNUS RUBRA)	PACIFIC CRABAPPLE (MALUS FUSCA)	BITTER CHERRY (PRUNUS EMARGINATA)
A	3.0	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
B1	1.0	--	20	20	20	--	--	--	--	--	2	2	2	--	--	--	--
B2	0.5	--	3	3	3	--	--	--	--	--	1	1	1	--	--	--	--
C	0.4	--	4	4	4	--	--	--	--	--	--	--	--	--	--	--	--
D1	--	9.8	--	--	97	97	96	97	97	90	--	--	--	30	28	28	30
D2	--	7.5	--	--	113	113	111	113	111	120	--	--	--	35	33	33	34
E	--	15.7	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

NO.	DATE	BY	REVISION

NOTICE  
0 1/2 1  
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU DESIGNED  
EJJ DRAWN  
BVO CHECKED




**CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1**

**WORK ZONE RESTORATION  
AND PLANTING PLAN**

PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021

G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-L.dwg L-2 3/11/2021 9:42 AM JUSTIN.DEUEL 23.0s (LMS Tech)



PLAN  
SCALE: 1"=40'

**LEGEND**

 INVASIVE SPECIES REMOVAL AREA, SEE NOTE 3

**NOTES:**


1. REMOVAL OF INVASIVE SPECIES OUTSIDE OF CONSTRUCTION ZONE TO BE COMPLETED BY HAND OR WITH THE USE OF SMALL MECHANICAL HAND TOOLS AS APPROVED BY ENGINEER.
2. INSTALL EROSION CONTROL MATTING AND UPLAND SEED MIX USING LOW IMPACT METHODS IN ALL CLEARED AREAS LARGER THAN 25 SQUARE FEET, SEE DETAIL 6, SHEET L-4. UPLAND SEED MIX PER SEED MIXES LEGEND ON SHEET L-1.
3. VEGETATED CORRIDOR REQUIRING INVASIVE SPECIES REMOVAL TO BE CLEARLY MARKED IN THE FIELD BY CONTRACTOR. SEE CWS SPL CONDITION 21 FOR REQUIREMENTS.
4. ALL EXISTING TREES SHOWN ON THIS SHEET ARE TO BE PRESERVED DURING CONSTRUCTION. SEE SHEET C-1 FOR TREE PROTECTION AND REMOVAL REQUIREMENTS.

NO.	DATE	BY	REVISION

NOTICE  
0 1/2 1  
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU DESIGNED  
EJJ DRAWN  
BVO CHECKED





  
**CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1**

**INVASIVE NON-NATIVE SPECIES  
REMOVAL AND RESTORATION**

PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021

G:\PD\Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-L.dwg L-3 3/11/2021 9:44 AM JOEY.URNES 23.0s (LMS Tech)




INSTALL ONSITE TEMPORARY IRRIGATION SYSTEM PER SPECIFICATIONS

FURNISH & INSTALL:  
245 LF - 1" / 2" PVC PIPING,  
SEE NOTE 2

FURNISH & INSTALL:  
1-IRRIGATION CONTROLLER,  
SEE NOTE 1  
1-TYPICAL BACKFLOW  
PREVENTER, SEE COS STD  
DWG W-70 THIS SHT

FURNISH & INSTALL:  
1-2" WATER METER  
SEE COS STD DET  
DWG W-60 THIS SHT

HOT TAP EXIST 8" WATER SERVICE  
FURNISH & INSTALL:  
1-2" SERVICE SADDLE  
18 LF - 2" COPPER PIPE  
1-2" CORP STOP,  
SEE NOTE 4




**PLAN**  
SCALE: 1"=20'

**NOTES:**


- IRRIGATION CONTROLLER TO BE BATTERY POWERED WITH A MINIMUM TWO-YEAR BATTERY LIFE SPAN, MULTI-ZONE MODEL IS ACCEPTABLE.
- TEMPORARY IRRIGATION PIPING MAY BE INSTALLED ABOVE GRADE FROM BACKFLOW PREVENTER TO ONSITE IRRIGATION SYSTEM.
- INSTALL UPLAND SEED MIX USING LOW IMPACT METHODS IN ANY DISTURBED AREAS ASSOCIATED WITH TEMPORARY IRRIGATION INSTALLATION. UPLAND SEED MIX PER SEED MIXES LEGEND ON SHEET L-1.
- CONTRACTOR TO REMOVE TEMPORARY IRRIGATION PIPING, IRRIGATION CONTROLLER, BACKFLOW PREVENTER, WATER METER, AND COPPER PIPING UP TO EXISTING WATER MAIN AFTER PLANT ESTABLISHMENT PERIOD ACCEPTANCE. INSTALL 2" PLUG IN SERVICE SADDLE.
- PROTECT EXISTING RETAINING WALL IN PLACE DURING 2-INCH SERVICE REMOVAL.
- CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ANNUAL HYDRANT PERMIT FROM CITY OF SHERWOOD, AS REQUIRED FOR TEMPORARY IRRIGATION.

**NOTICE**




IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU  
DESIGNED  
EJJ  
DRAWN  
BVO  
CHECKED



**murraysmith**



**CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1**

**TEMPORARY IRRIGATION PLAN**


SHEET

L-3

31 of 32

PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021


G:\PDX\_Projects\19\2481 - Rock Creek Trunk Upsizing Phase 1\CAD\Sheets\19-2481-OR-L.dwg L-4 3/11/2021 9:42 AM JUSTIN.DEUEL 23.0s (LMS Tech)



**SMALL SHRUB PLANTING**

SCALE: NTS


1  
-



**SLOPED AREA SHRUB PLANTING**

SCALE: NTS


4  
-



**DECIDUOUS TREE PLANTING**

SCALE: NTS

2  
-




NOTE:

- 1. MINIMUM SPACING BETWEEN TREES TO BE 8 FEET. MINIMUM SPACING BETWEEN SHRUBS OR TREES AND SHRUBS TO BE 5 FEET.

**RANDOM PLANTING PATTERN**

SCALE: NTS


5  
-



**EVERGREEN TREE PLANTING**

SCALE: NTS

3  
-



**EROSION CONTROL MATTING INSTALLATION**

SCALE: NTS

6  
-

**GENERAL LANDSCAPE NOTES:**

1. THE CONTRACTOR SHALL EXAMINE FINISH SURFACE, GRADES, TOPSOIL QUALITY AND DEPTH. DO NOT START ANY WORK UNTIL UNSATISFACTORY CONDITIONS HAVE BEEN CORRECTED. VERIFY LIMITS OF WORK BEFORE STARTING.
2. CONTRACTOR TO REPORT ALL DAMAGES TO EXISTING CONDITIONS AND INCONSISTENCIES WITH PLANS TO THE ENGINEER.
3. IMPROVE EXISTING SOIL WITH ORGANIC MATTER BY ADDING 4" COMPOST AND TILL INTO TOP 12" OF TOPSOIL PRIOR TO PLANTING AT LOCATIONS DETERMINED BY ENGINEER.
4. PLANTINGS SHALL BE TAGGED FOR DORMANT SEASON IDENTIFICATION AND SHALL REMAIN ON PLANT MATERIAL AFTER PLANTING FOR MONITORING PURPOSES.
5. TREES AND SHRUBS PLANTED IN UPLAND AREAS SHALL BE MULCHED A MINIMUM OF THREE INCHES IN DEPTH AND 18 INCHES IN DIAMETER.
7. BACKFILL MATERIAL FOR TREE AND SHRUB PLANTING SHALL CONTAIN: ONE-PART FINE GRADE COMPOST TO ONE-PART TOPSOIL BY VOLUME, BONE MEAL PER MANUFACTURER'S RECOMMENDATION, AND SLOW RELEASE FERTILIZER PER MANUFACTURER'S RECOMMENDATION.
8. CONTRACTOR SHALL OBTAIN WRITTEN APPROVAL FOR ALL PLANT MATERIAL SUBSTITUTIONS FROM THE ENGINEER PRIOR TO INSTALLATION. PLANT SUBSTITUTIONS WITHOUT PRIOR WRITTEN APPROVAL THAT DO NOT COMPLY WITH THE DRAWINGS AND SPECIFICATIONS MAY BE REJECTED AT NO COST TO THE OWNER. THESE ITEMS MAY BE REQUIRED TO BE REPLACED WITH PLANT MATERIALS THAT ARE IN COMPLIANCE WITH THE DRAWINGS.
9. ALL PLANT MATERIALS SHALL BE NURSERY GROWN WITH HEALTHY ROOT SYSTEMS AND FULL BRANCHING, DISEASE AND INSECT FREE AND WITHOUT DEFECTS SUCH AS SUN SCALD, ABRASIONS, INJURIES AND DISFIGUREMENT.
10. ALL PLANT MATERIAL SHALL BE INSTALLED AT THE SIZE AND QUANTITY SPECIFIED. WITHOUT APPROVAL, THE ENGINEER IS NOT RESPONSIBLE FOR SUB-STANDARD RESULTS CAUSED BY REDUCTION IN SIZE AND/OR QUANTITY OF PLANT MATERIALS.
11. NEW TREES THAT ARE PLANTED TO MEET THE EFFECTIVE CANOPY REQUIREMENTS SHALL CONFORM TO THE APPLICABLE STANDARDS OF CLEAN WATER SERVICES. THEY SHALL BE PLANTED IN ACCORDANCE WITH THE AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI) STANDARDS FOR TREE PLANTING (A300, PART 6) AND ADDITIONAL STANDARDS ADOPTED BY THE OREGON LANDSCAPE CONTRACTORS BOARD. NURSERY STOCK SHALL MEET THE REQUIREMENTS OF THE AMERICAN ASSOCIATION OF NURSERYMEN FOR NURSERY STOCK (ANSI Z60.1) FOR GRADE NO. 1 OR BETTER. DOUBLE STAKE TREES IF NEEDED FOR STABILITY DURING THE ESTABLISHMENT PERIOD.
12. CONTRACTOR SHALL PROVIDE TWO-YEAR PLANT ESTABLISHMENT PERIOD TO MAINTAIN PLANTS IN A VIGOROUS GROWING CONDITION. INSURE PLANTING AREAS ARE FREE OF INVASIVE WEEDS. PLANTS SHALL BE FREE OF INSECTS AND DISEASES WHILE SHOWING SIGNS OF CONTINUING HEALTH. THE PLANT ESTABLISHMENT PERIOD BEGINS IMMEDIATELY AFTER THE COMPLETION OF ALL PLANTING OPERATION AND WRITTEN NOTIFICATION TO THE ENGINEER.

NO.	DATE	BY	REVISION

NOTICE  
0 1/2 1  
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

JJU DESIGNED  
EJJ DRAWN  
BVO CHECKED



**CITY OF SHERWOOD  
ROCK CREEK  
SANITARY TRUNK LINE  
UPSIZING PROJECT -  
PHASE 1**

**RESTORATION AND PLANTING DETAILS**

PROJECT NO.: 19-2481.402 SCALE: AS SHOWN DATE: FEBRUARY 2021

SHEET  
L-4  
32 of 32