



SW Sunset Blvd and SW Pine Street Sanitary Sewer Extensions

DATE: June 24, 2016

ADDENDUM NO. 2

Addition/Change to the Contract Documents

The work provided for in this addendum shall become a part of the drawings and specifications for this project.

1. The SW Pine Street Bid Schedule and the Special Provisions have the 8-Inch, PVC, ASTM 3034 and 4-Inch, PVC, ASTM 3034 listed as SDR 26. References to SDR 26 shall be changed to SDR 35. Page 33 of the Special Provisions has been changed and the revised page has been hereby attached. A revised SW Pine Street Bid Schedule has been hereby attached.

This ADDENDUM shall be signed and attached to the Bidder's Proposal and shall subsequently become part of the Contract Documents.

Company Name	
Contractor Name	
Contractor Signature	
Date	

Comply with Section 442 of the Standard Specifications.

SECTION 00445 – SANITARY, STORM, CULVERT, SIPHON, AND IRRIGATION PIPE

Comply with Section 00445 of the Standard Specifications modified as follows:

Add the following subsection:

00445.76 Manhole Testing -Testing of sanitary manholes (hydrostatic, vacuum) shall be conducted by the contractor according to the requirements of Clean Water Services "Design and Construction Standards Manual". The cost of cleaning and testing of manholes is incidental.

All new sanitary sewer manholes shall be tested.

Any additional manhole testing required due failed tests/inspection, shall be performed at the contractor's expense.

Add the following subsection:

00445.77 Cleaning of Sanitary and Storm Facilities – All sanitary piping and manholes shall be cleaned and free of sediments, debris and obstructions prior to final acceptance. Any sediments, debris and obstructions entering existing catch basins, storm piping, storm manholes, ditches and water quality facilities, as determined by the Engineer, shall be cleaned by the contractor. The cost of cleaning is incidental.

Add the following pay items and bulleted items to the following subsection as follows:

00445.91 Payment –

Pay Item	Unit of Measurement
(a) 8-Inch, PVC, ASTM 3034, SDR 26 35 Pipe.....	Foot (Revised per Addendum #2)
(b) 4-Inch, PVC, SDR 26 35 Sanitary Lateral	Foot (Revised per Addendum #2)
(c) 4-Inch, Ductile Iron, Sanitary Lateral	Foot

No separate or additional payment will be made for:

- Trench stabilization
- Securing existing utilities to perform trench excavation, dewatering, pipe installation and trench bedding and backfill

SECTION 00470 – MANHOLES, CATCH BASINS, AND INLETS

Comply with section 00470 of the Standard Specifications.

SECTION 00490 – WORK ON EXISTING SEWERS AND STRUCTURES

Comply with Section 00490 of the Standard Specifications modified as follows:

**SUNSET BLVD & PINE ST SANITARY SEWER EXTENSIONS
 (SW PINE STREET SANITARY SEWER BID SCHEDULE – REVISED PER ADDENDUM #2)**

Item No.	Spec Section	Description	Unit	Quantity	Unit Price	Unit Total Cost
PART 00200 -- TEMPORARY FEATURES AND APPURTENANCES						
1	00210	Mobilization	LS	1		
2	00225	Temporary Work Zone Traffic Control, Complete with Flaggers	LS	1		
3	00280	Erosion Control	LS	1		
PART 00300 -- ROADWORK						
4	00305	Construction Survey Work	LS	1		
5	00310	Removal of Structures and Obstructions	LS	1		
PART 00400 -- DRAINAGE & SEWERS						
6	00405	Trench Foundation	CY	5		
7	00405	Rock Excavation	CY	5		
8	00405	Boulder Excavation	CY	5		
9	00415	Mainline Video Inspection	FOOT	633		
10	00415	Pre-Construction Video Inspection	LS	1		
11	00445	8-Inch, PVC, ASTM 3034, SDR 35 Pipe	FOOT	633		
12	00445	4-Inch, PVC, ASTM 3034, SDR 35 Sanitary Lateral, Green	FOOT	178		
13	00470	Concrete Sanitary Sewer Manhole	EACH	3		
14	00470	Concrete Sanitary Sewer Cleanouts, 4-inch	EACH	10		
15	00490	Connection to Existing Manhole	EACH	1		
16	00490	Connection to Existing Piping	EACH	8		
17	00490	Filling 6" Clay Pipe with CLSM	FT	226		
18	00495	Trench Resurfacing, temporary ACP, 2-Inch Depth	SY	325		
19	00495	Trench Resurfacing, ACP, 5-Inch Depth	SY	395		
PART 01000 -- RIGHT OF WAY DEVELOPMENT AND CONTROL						
20	01030	Yard Restoration	LS	1		
TOTAL SW PINE STREET SANITARY SEWER BID						

SW PINE STREET SANITARY SEWER BID WRITTEN IN WORDS:

_____ DOLLARS AND _____ CENTS

In the event of discrepancy, the amount in words shall dictate.

In accordance with the provisions of the Oregon Standard Specifications for Construction, 2015 Edition as modified by these bid documents, the undersigned Bidder submits the following Bid Schedule with the understanding that City reserves the right to increase, decrease, or completely eliminate quantities as set forth in 00120.20. Also, the Bidder offers to do the work, whether quantities area changed (increased or decreased) in accordance with 00195.20, or not changed, at the unit rate price stated in the following Bid Schedule:

Signature of Authorized Agent

Company Name

Printed Name

Date
