





STANDARD DRAWING TITLE		DRAWING NUMBER
4" MCT-II METER INSTALLATION BY CONTRACTOR		W-62
Any alteration of this drawing may not be associated in any way with the City of Sherwood Standard Drawings.	SCALE	REVISION DATE
	N.T.S.	2022.08.15



QTY	DESCRIPTION
1	UTILITY VAULT 675-WA-730 WITH SYRACUSE DOOR CHD-11AL AND OSHA APPROVED LADDER SEE NOTE 1 EXTERIOR TO BE SEALED WITH CRYSTAL SEAL OR APPROVED EQUAL
1	4" PIPE STAND "STANDON"
1	4" GATE VALVE FLG x MJ
1	4" GATE VALVE MJ
1	4" GATE VALVE FLG
1	4"x4" TEE MJ x FLG
1	4"x4" TEE MJ
2	4" 90° BENDS MJ
8	4" MEGALUG RETAINER GLANDS
1	4" D.I. SPOOL FLG x PE 5 FT LG
1	4" D.I. SPOOL FLG x PE 10 FT LG
1	4" DUCTILE IRON PIPE 30 LF
1	OPTIONAL SUMP PUMP "GRUNDFOSS" MODEL "THE BOSS" 1/3 HP 115V 1/2" DISCHARGE PUMP WITH FLOAT SWITCH AND 1" DISCHARGE REFER TO DET W-42 & W-44
	MISC PIPING FOR DISCHARGE WITH INLINE CHECK VALVE CHECK VALVE

NOTES:

- CONTRACTOR SEAL ALL OPENINGS IN VAULT WITH NON SHRINK GROUT.
- CONTRACTOR TO INSTALL CONCRETE BALLAST 3 CU. YD. MIN. AROUND BASE OF VAULT IN AREAS WHERE FLOODING OR HIGH GROUND WATER EXIST.
- ALL MATERIALS SHALL BE AS NAMED OR EQUAL. SUBMIT ALTERNATES FOR APPROVAL.
- THRUST BLOCK 1'-0" MIN. THICKNESS.